


15-051-00546-00-00

WELL PLUGGING RECORD

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 13 Twp. 11S Rge. 20 ~~(EX)~~ (W)
Location as "NE/CNW*SW*" or footage from lines SE SE NE
Lease Owner Braden Drilling Company
Lease Name Shubert "A" #1 Well No. 1
Office Address 814 Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Jan. 1, 1955 19
Application for plugging filed Jan. 5, 1955 19
Application for plugging approved 19
Plugging commenced Jan. 5, 1955 19
Plugging completed Jan. 5, 1955 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3762 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 180'. Set bottom plug. Cemented with 15 sacks cement.
Filled plug to 30' with heavy mud, Set top plug, Cemented with 10 sacks cement.
Filled cellar with surface top soil.

1-12-1955

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Braden Drilling Company
Address 814 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Louis E. Potucek (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Louis E. Potucek
814 Union Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of January, 19 55

My commission expires April 29, 1957
Norma Riskey Notary Public.

PLUGGING
FILE SEC 13 11 R 20W
BOOK PAGE 89 LINE 2

15-051-00546-00-00

SHUBERT "A" #1

13-11S-20W
SE SE NE
Ellis County, Kansas

OPERATOR: Braden Drilling Company

Elevation: 2055' DF

CONTRACTOR: Braden Drilling Company

Commenced: 12-20-54

Completed: 1-5-55

Casing Record:

195' of 8 5/8" surface. Set with 150 sx Cement 100# cal. Chloride.

Clay and Blue Shale	195	
Shale and Shells	220	
Sand and Shale	700	
Shale, Sand and Shells	1220	
Shale and Shells	2020	
Lime	2335	
Lime and Shale	2455	
Lime and Shale	3150	
Lime	3634	
Conglomerate	3745	
Lime	3762	TD RB

STATE OF KANSAS,) (SS:-
SEDGWICK COUNTY,)

I hereby certify that the above information is true and correct as revealed by the records of the Braden Drilling Company.

Norma Risher

Subscribed and sworn to before me this 11 day of January 1955

Norma Risher
Notary Public

My commission expires: April 29, 1957

1-12-1955

