

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Anadarko Petroleum Corporation

Address: PO Box 1330 Houston, TX 77251-1330

Phone: (832) 636-8380 Operator License #: 4549

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 02/18/2009 (Date)

by: Lin Reimer (KCC District Agent's Name)

Is ACO-1 filed? [x] Yes [] No If not, is well log attached? [] Yes [] No

Producing Formation(s): List All (If needed attach another sheet)

Chase Depth to Top: 2658 Bottom: 2738 T.D. 2760

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15- 175-00538 - 0000

Lease Name: Printz A

Well Number: 1

Spot Location (QQQQ): - - C - NE

1320 Feet from [x] North / [] South Section Line

1320 Feet from [x] East / [] West Section Line

Sec. 2 Twp. 35 S. R. 34 [] East [x] West

County: Seward

Date Well Completed: 04/26/1961

Plugging Commenced: 02/17/2009

Plugging Completed: 02/19/2009

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put in, Pulled out. It contains two rows of data for the 'Chase' formation.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Mixed 200 lbs hulls & 20 sks cmt; pump plug from 2658' to 2400'. TOH w/tbg to 1650'. Pump 20 sks cmt, pump plug from 1650' to 1400'. TOH w/tbg. Shot 4.5" csg loose @ 495'. Pulled csg; pump 50 sks cmt to 395'. Mix 10 sks cmt and pump from 40' to surface. Cut off and capped 8-5/8" csg 3' below surface.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License #: 31151

Address: Rt. 1 Box 49BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.


(Signature) Diana Smart

(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 2nd day of March, 2009

Bertha Neff Notary Public My Commission Expires: 12-27-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED KANSAS CORPORATION COMMISSION

MAR 04 2009

CONSERVATION DIVISION WICHITA KS

Handwritten initials 'PT'