

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Anadarko Petroleum Corporation

Address: PO Box 1330 Houston, TX 77251-1330

Phone: (832) 636-8380 Operator License #: 4549

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 02/24/09 (Date)

by: Jack Maclaskey (KCC District Agent's Name)

Is ACO-1 filed? [x] Yes [ ] No If not, is well log attached? [ ] Yes [ ] No

Producing Formation(s): List All (If needed attach another sheet)

Lower Chester Depth to Top: 6170 Bottom: 6180 T.D. 6400

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15- 175-20699 - 00 00

Lease Name: Hitch

Well Number: 1-14

Spot Location (QQQQ): - C - NW - SW

1980 Feet from [ ] North / [x] South Section Line

660 Feet from [ ] East / [x] West Section Line

Sec. 14 Twp. 33 S. R. 34 [ ] East [x] West

County: Seward

Date Well Completed: 07/12/1983

Plugging Commenced: 02/23/2009

Plugging Completed: 02/26/2009

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put in, Pulled out)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Mixed 250 lbs bulls & 25 sks cnt; pump plug from 6170' to 5970'. Shot 5.5" csg loose @ 2526'. Pulled 20' hit tight spot. Shot off @ 1690'. Mix and pump 50 sks cnt from 1680' 1530'. Pull csg to 500'. Mix and pump 40 sks cnt from 600' to 480'. Pull csg to 40'. Mix and pump 10 sks cnt from 40' to surface. Cut off and capped 8-5/8" csg 3' below surface.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License #: 31151

Address: Rt. 1 Box 49BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Diana Smart

(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 2nd day of March, 2009

Bertha Nefe Notary Public My Commission Expires: 12-27-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

