

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 04 2009
CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oil Producers of Kansas

Address: 1710 Waterfront Parkway, Wichita, KS 67201

Phone: (316) 681-0231 Operator License #: 8061

Type of Well: Oil/Gas KCC PKT per ACO-1 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

SWOPE Depth to Top: 4759 Bottom: 4761 T.D. _____
Lansing Depth to Top: 4430 Bottom: 4440 T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 033-21,442 - 0000

Lease Name: Huck

Well Number: 1-27A

Spot Location (QQQQ): E/2 - SW - NW - NE

990 Feet from North / South Section Line

2080 Feet from East / West Section Line

Sec. 27 Twp. 34 S. R. 16 East West

County: Comanche

Date Well Completed: 9-21-05

Plugging Commenced: 2-6-09

Plugging Completed: 2-11-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1152	
				4 1/2	5099	3740

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 30 sacks, 200# hulls down 4 1/2" casing, dug cellar, unpacked casing head, set floor, checked hole, tagged cement at 4320', pulled slips, had 26" stretch, ripped casing at 3910', worked pipe, ripped casing at 3740', pipe came free, pulled casing up to 1170', pumped 15 gel, 50 sacks, 100# hulls at 1170', pulled to 250', pumped 40 sacks, 100# hulls, pulled to 40', pumped 20 sacks to surface, topped off with 40 sacks, cleaned up location.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Oil Producers of Kansas

State of Kansas County, Sedawick, ss.

Oil Producers Inc. of Kansas (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) TJ

(Address) 1710 Waterfront Parkway Wichita KS 67206

SUBSCRIBED and SWORN TO before me this 27 day of February, 2009

Lora A. Zehr My Commission Expires: May 5, 2010
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT