

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior INC
Address: P.O.Box 399 Garden City, Ks 67846
Phone: (620) 275 -2963 Operator License #: 4058
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 2-16-09 (Date)
by: Rich Williams/ District 4 (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3334' Bottom: 3336' T.D. 3336

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 009-23,462 - 00 - 00
Lease Name: Lang
Well Number: B-3
Spot Location (QQQQ): C - E/2 - E/2 - NE
3960 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 4 Twp. 17 S. R. 12 East West
County: Barton
Date Well Completed: 2-27-1984
Plugging Commenced: 2-18-09
Plugging Completed: 2-18-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0	300	8-5/8"	300	None
	Production	0	3334	4-1/2"	3334	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforate 2 holes @ 1400' & 660', ran tbg. to 3300' pump 12 sks gel & 40 sks cement, 100#s hulls, pull tbg, to 1400'. pump, 40 sks cement & 100# hulls, pull tbg, to. 660', circulate cement w/ 90 sks & 300#s hulls, pull tbg, hookup to ann. pump, 25 sks cement, hookup to 4-1/2" csg. top off w/ 45 sks cement, (cement 60/40 poz 4% gel) cut off csg, fill cellar,

Name of Plugging Contractor: Swift Services INC License #: 32382 **KANSAS CORPORATION COMMISSION**

Address: P.O.Box 466 Ness city, Ks 67560

MAR 02 2009

Name of Party Responsible for Plugging Fees: American Warrior INC

RECEIVED

State of Kansas County, Finney, ss.

Kevin Wiles Sr. / Production Supt.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

ERICA KUHLMEIER
Notary Public - State of Kansas
My Appt. Expires 09-12-09

(Signature) [Handwritten Signature]

(Address) P.O.Box 399 Garden City, Ks 67846

SUBSCRIBED and SWORN TO before me this 07th day of February, 2009

[Handwritten Signature]
Notary Public

My Commission Expires: 09-12-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten Initials]