

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

MAR 05 2009

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

WELL PLUGGING RECORD RECEIVED

K.A.R. 82-3-117

Lease Operator: Rama Operating Company, Inc.

Address: P.O. Box 159 Stafford, Kansas 67578

Phone: (620) 234-5191 Operator License #: 3911

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: B.J. Hope (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 155-21,384-0000

Lease Name: Richardson

Well Number: 1-21

Spot Location (QQQQ): C - SW - SE - NW

2310 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 21 Twp. 22 S. R. 7 East West

County: Reno

Date Well Completed: _____

Plugging Commenced: 2-25-09

Plugging Completed: 2-26-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	263'	None
				5-1/2"	3599'	2736'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set BP @2900' with 5 sxs. cement on top. Cut casing loose @2736', pulled up to 1050', pumped 15 sxs. gel and 35 sxs. cement. Pulled up to 575', pumped 35 sxs. cement, pulled up to 315', pumped 35 sxs. cement, pulled up to 40' and circulated 40 sxs. cement to surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Rama Operating Co., Inc.

State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) *Mic J...*

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 3rd. day of March, 20 09

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PK