

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD RECEIVED K.A.R. 82-3-117

MAR 05 2009

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: John J. Darrah
Address: 225 N. Market #300 Wichita, Kansas 67202
Phone: (620) 786-4046 Operator License #: 5088
Type of Well: Oil Docket #:
The plugging proposal was approved on:
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-053-00794-0000
Lease Name: Rathburn
Well Number: A-4
Spot Location (QQQQ): - NW - SW - NE
330 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 16 Twp. 17 S. R. 8 East West
County: Ellsworth
Date Well Completed: 1951
Plugging Commenced: 2-17-09
Plugging Completed: 2-18-09

KCC
ACT

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing sizes of 8-5/8" and 5-1/2" with depths of 204' and 3268'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Plugged off bottom with sand to 3130' and 5 sxs. cement. Perforated casing @1050', 750' and 270'. Ran 2-3/8" tubing to 1050', pumped 10 sxs. gel and 35 sxs. cement. pulled up to 750', pumped 35 sxs. cement, pulled up to 270' and circulated 130 sxs. cement to surface, topped off with 20 sxs. cement, 60/40 pos. 4% gel.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: John J. Darrah
State of Kansas County, Rice, ss.


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 3rd day of March, 20 09

[Signature] Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PK9