

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

MAR 05 2009

RECEIVED

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Rama Operating Company, Inc. Address: P.O. Box 159 Stafford, Kansas 67578 Phone: (620) 234-5191 Operator License #: 3911 Type of Well: SWD Docket #: D-15,066 The plugging proposal was approved on: by: Richard Lacey Is ACO-1 filed? Producing Formation(s):

API Number: 15-185-12786-000 Lease Name: Miller "B" Well Number: 1 Spot Location (QQQQ): C - SW - NE - SE 1650 Feet from North / South Section Line 990 Feet from East / West Section Line Sec. 14 Twp. 24 S. R. 14 East West County: Stafford Date Well Completed: Oct. 1950 Plugging Commenced: 2-12-09 Plugging Completed: 2-16-09

KCC PKT per OPS

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing sizes of 8-5/8" and 4-1/2" with depths of 809' and 3868'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. Plugged off bottom with sand to 3580' and 4 sxs. cement. Perforated casing @830', ran 2-3/8" tubing to 830'. pumped 70 sxs. cement, layed down, tubing, pumped 50 sxs. cement, shut well in, on vacuum, waited 30 mins, pumped 30 sxs., waited 1 hour, pumped 30 sx cement, 60/40 pos, 4% gel. Plugging Complete

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529 Address: P.O. Box 467 Chase, Kansas 67524


Name of Party Responsible for Plugging Fees: Rama Operating Co., Inc. State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] (Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 3rd. day of March, 20 009

[Signature] Notary Public My Commission Expires:



PKT