

MAR 09 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD CONSERVATION DIVISION
WICHITA, KS
K.A.R. 82-3-117

Lease Operator: VESS OIL CORPORATION
Address: 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206
Phone: (316) 682-1537 Operator License #: 5030

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 01/09 (Date)
by: Ray Dinkel (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 2740 Bottom: 2938 T.D. 3070
LKC Depth to Top: 3013 Bottom: 3245 T.D. 3070
Reagan Depth to Top: 3300 Bottom: 3360 T.D. 3360

API Number: 15 - 167-05988 - 0000
Lease Name: Rusch B
Well Number: 4
Spot Location (QQQQ): _____ - S/2 - N/2 - SW
1650 Feet from North / South Section Line
3960 Feet from East / West Section Line
Sec. 19 Twp. 12 S. R. 15 East West
County: Russell
Date Well Completed: 5/18/58
Plugging Commenced: 2/10/09
Plugging Completed: 2/11/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	953	-
				5-1/2"	3300	-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Perf Tech. Perforate - 1600'. TIH w/tbg to 2989'. Spotted 40 sx 60/40 poz w/4% gel, 3% CC and 100# hulls on bottom w/15 sx gel on top
Pulled tbg to 2200' and set 1 hr. Ran back to 2989' w/tubing. Spotted another 40 sx same cement w/1% CC and 100# hulls w/11 sx gel.
Pulled tbg to 1612'. Spotted 80 sx same cement - good circulation. Pulled to 806'. Circulated cement to surface w/80 sx same cement w/200# hulls.
TOH w/tubing. Topped off w/10 sx. Pumped 10 sx same cement down 8 5/8" - 500#, SI. Approved by Ray Dinkel w/KCC.

Name of Plugging Contractor: Smoky Hills Well Service License #: 32452 KCCPKT
Allied Cementing Co., Inc.
Address: P.O. Box 31, Russell, KS 67665-0031

Name of Party Responsible for Plugging Fees: Vess Oil Corporation


State of Kansas County, Sedgwick, ss.

Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 6th day of March

Michelle D. Henning My Commission Expires: _____
Notary Public



[Handwritten initials]

Sohio Petroleum Company
Rusch "B" #4

CS/2 N/2 SW Sec. 19-12-15
Russell County, Kansas

R.T.D. 3302'

CONTRACTOR: Bennett & Roberts Drilling, Inc.

Commenced 4/30/58
Completed 5/12/58

8 5/8" Set @ 952 1/2' w/500 sx cnt
5 1/2" Set @ 3298' w/175 sx cement

Surface Clay	35'
Shale & Shells	255
Shale & Sand	460
Iron	484
Sand & Iron	495
Sand	525
Shale	580
Sand	620
Sand & Shale	670
Red Bed & Shale	942
Anhydrite	975
Lime & Shale	1180
Shale & Shells	1720
Lime & Shale	1765
Lime	1800
Lime & Shale	1840
Lime	1920
Lime & Shale	2325
Lime	2380
Shale & Lime	2860
Lime	2975
Lime & Shale	3047
Lime	3155
Lime & Shale	3205
Lime	3280
Lime & Shale	3302

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 09 2009

CONSERVATION DIVISION
WICHITA KS

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is true and correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By John R. Twinn

Subscribed and sworn to before me this 13th day of May, 1958.

Clara L. Hummel
Notary Public

My Commission Expires 6/17/58

ALLIED CEMENTING CO., LLC. 34889

ATTN TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Russell

DATE <u>2-11-09</u>	SEC. <u>19</u>	TWP. <u>12</u>	RANGE <u>15</u>	CALLED OUT	ON LOCATION	JOB START <u>2:00PM</u>	JOB FINISH <u>3:00PM</u>
OWNER <u>RUSCH</u>	WELL # <u>B-2</u>	LOCATION <u>Giorham 1E 2N 1/2W 1/2N</u>				COUNTY <u>Russell</u>	STATE <u>Kansas</u>
DROR NEW (Circle one) <u>4</u>							

CONTRACTOR (Smoky Hill's Well Service) OWNER _____
 TYPE OF JOB PLUG ABANDONED well
 HOLE SIZE 7 7/8 T.D. _____
 CASING SIZE 5 1/2 DEPTH 3352
 TUBING SIZE 2" DEPTH @ 2989
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 500 # MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT 10.8BL

CEMENT (USED 260SK)
 AMOUNT ORDERED 375sx 60/40 4% Gel
11 sx Gel outside
500 # Hulls on side

COMMON	<u>156 SK</u>	@ <u>13.50</u>	<u>2106.00</u>
POZMIX	<u>104 SK</u>	@ <u>7.55</u>	<u>785.20</u>
GEL	<u>22 SK</u>	@ <u>20.25</u>	<u>445.50</u>
CHLORIDE	<u>2 SK</u>	@ <u>51.50</u>	<u>103.00</u>
ASC	_____	@ _____	_____
<u>Hull's 500 #</u>	_____	@ <u>31.05</u>	<u>155.25</u>
_____	_____	@ _____	_____
_____	_____	@ _____	_____
_____	_____	@ _____	_____
_____	_____	@ _____	_____
_____	_____	@ _____	_____
_____	_____	@ _____	_____
_____	_____	@ _____	_____
_____	_____	@ _____	_____
HANDLING	<u>375 TOTAL SX</u>	@ <u>2.25</u>	<u>843.75</u>
MILEAGE	<u>10 Ton Mile</u>	@ <u>10 #</u>	<u>600.00</u>
TOTAL	_____	_____	<u>5038.70</u>

EQUIPMENT

PUMP TRUCK # 409 CEMENTER Glenn HELPER Bob
 BULK TRUCK # 473 DRIVER Rocky
 BULK TRUCK # _____ DRIVER _____

REMARKS:

2" Tubing @ 2989 Spot 40sx Cement
3% CC, Pulled Above WAIT 1HR. Ran
Back to 2989 did NOT TAG any Cement.
Decide to Spot 11SX Gel & 40 SX 1%CC
Cement w/ 100# Hulls. Pulled to 1612
& Spot 80 SX Cement, 200 #
Hull's. Pulled up to 800' & Circulated
Cement to Surface w/ 80 SX & 200 # Hulls.
Topped off w/ 10SK Hole Stayed Fall.
8 5/8 Backside mixed 10 SX @ 1500# & SHUT IN @ 500'

SERVICE

DEPTH OF JOB	_____	_____
PUMP TRUCK CHARGE	_____	<u>1045.00</u>
EXTRA FOOTAGE	_____	@ _____
MILEAGE <u>16</u>	@ <u>7.00</u>	<u>112.00</u>
MANIFOLD	_____	@ _____
_____	_____	@ _____
_____	_____	@ _____
_____	_____	@ _____
_____	_____	@ _____
TOTAL	_____	<u>1157.00</u>

CHARGE TO: Vess Oil Corporation
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

RECEIVED
 KANSAS CORPORATION COMMISSION
 MAR 09 2009
 CONSERVATION DIVISION
 WICHITA, KS

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME _____
 SIGNATURE [Signature]

SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS
[Signature]