

15-195-20281-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Trego

County. Sec. 11 Twp. 11S Rge. (E) 22 (W)

Location as "NE/CNW/SW" or footage from lines C NW NW

Lease Owner F & M Oil Company

Lease Name KRAEMER Well No. #1

Office Address 603 Union Center, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 9 19 74

Application for plugging filed (verbal) June 9 19 74

Application for plugging approved (verbal) June 9 19 74

Plugging commenced June 9 19 74

Plugging completed June 9 19 74

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation Depth to top Bottom Total Depth of Well 3900' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	218'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st Plug set @ 800' with 70 sacks cement

2nd Plug set @ 225' with 20 sacks cement

3rd Plug set @ 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Jerry A. Langrehr*
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of June, 1974

Nancy E. Bledsoe
Nancy E. Bledsoe - Notary Public.

My commission expires April 8, 1978

15-195-20281-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	F & M Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	KRAEMER #1
LOCATION:	C NW NW Section 11-11S-22W Trego County, Kansas
GEOLOGIST:	R. D. (Gus) Messinger
SPUD DATE:	June 2, 1974
COMPLETION DATE:	June 9, 1974

0	341	Sand and Shale
341	1662	Shale and Sand
1662	1708	Anhydrite
1708	2220	Shale
2220	3243	Shale and Lime
3243	3501	Lime and Shale
3501	3900	Lime
	3900	Rotary Total Depth

Drilled 218' of 12½" hole. Set 8 5/8" surface casing at 218'. Cemented with 175 sacks Common Cement with 2% gel, 3% CACL. Cement circulated. Plug was down @ 2:15 a.m., June 2, 1974.

D & A: Set 1st Plug at 800' with 70 sacks cement, 2nd Plug at 225' with 20 sacks cement, 3rd Plug at 40' with 10 sacks cement. Plug was down @ 12:45 p.m., June 9, 1974. State Plugger: Bill Nichols.

<u>Sample Tops</u>	<u>Elevation</u>
Anhydrite 1662 (+538)	2200 K.B.
B/Anhydrite 1708 (+492)	2197 D.F.
	2191 G.L.

RECEIVED
STATE CORPORATION COMMISSION
6-13-1974
JUN 13 1974
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KRAEMER #1, C NW NW Section 11-11S-22W, Trego County, Kansas.

ABERCROMBIE DRILLING, INC.

By: *Jerry A. Langrehr*
Jerry A. Langrehr
Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 12th day of June, 1974.

Nancy E. Bledsoe
Nancy E. Bledsoe, Notary Public

My Commission Expires: April 8, 1978

