

12-31-2002
DEC 31 2002
KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-193 ~~2007-00-01~~ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Carmen Schmitt, Inc. KCC LICENSE # 6569
(owner/company name) (operator's)

ADDRESS P.O. Box 47 CITY Great Bend

STATE Kansas ZIP CODE 67530 CONTACT PHONE # (620 793-5100)

LEASE Nollette WELL# #1 SEC. 9 T. 10s R. 33 (East/West)

150'SW-C - SW - SW SPOT LOCATION/OOOO COUNTY Thomas

150 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

150 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 363' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 4488' CEMENTED WITH 145 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4352'-4358'/BP 4346'/4327'-4332'/4310'-4314'

ELEVATION 3178'/3183' T.D. 4822' PBDT 4434' ANHYDRITE DEPTH 2693'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING As per KCC

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Unknown

If not explain why? Not available

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Edward S. Nemnich PHONE# 620 587-3361

ADDRESS P.O. Box 231 City/State Claflin, KS 67525

PLUGGING CONTRACTOR D.S. & W. Well Servicing, Inc. KCC LICENSE # 6901
(company name) (contractor's)

ADDRESS P.O. Box 231, Claflin, KS 67525 PHONE # 620 587-3361

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Friday, January 3, 2003

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12/30/02 AUTHORIZED OPERATOR/AGENT: Edward S. Nemnich
(signature)

6/03

6/03



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Schmitt, Carmen, Inc.
PO Box 47
Great Bend, KS 67530

December 31, 2002

Re: NOLLETTE #1
API 15-193-20079-00-01
CSWSW 9-10S-33W, 150 FNL 150 FEL
THOMAS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

15-193-20079-00-01

PRATHER OIL CORPORATION
 418 PETROLEUM BLDG. #1-9 NOLLETTE "OWWO" 9-10-33W
 AMARILLO, TX 79101 150'SW.
 CONTR MURFIN DRLG. CO. C SW SW
 CTY THOMAS

GEOL _____ FIELD WC(1/4 NW OF NOLLETTE;
 OVER 1 MI FROM PROD)

+	+	+
+	+	+
+	+	+

 ELV 3183 KB SPD 11/15/83 CARD ISSUED 4/12/84 IP P 20 BO & 10 BWPD
 API 15-193-20,079-A LKC 4310-4332 OA

LOG	Tops	Depth/Datum
ANH	2693+	490
B/ANH	2722+	461
HEEB	4082-	899
LANS	4123-	940
STARK SH	4341-	1158
BKC	4400-	1217
MARM	4422-	1239
L CHER	4615-	1432
B/CHER	4710-	1527
MISS	4721-	1538
LTD&RTD	4822-	1639

OLD INFO: OPERATOR WAS DONALD C. SLAWSON & PETRO-
 LEUM, INC., #1 'M' NOLLETTE, SPD 5/15/76, SET 8 5/8 " 363 /
 250SX, (CARD ISSUED 6/9/76), CONTR: SLAWSON DRILLING CO.,
 INC., GEOL: GEORGE MUELLER
 DST (1) 4284-4320 (LKC) / 30-45-45-60, REC 5' MDY OIL, 125'
 HOCM, SIP 1264-1211#, FP 35-70 / 70-88#
 DST (2) 4319-4347 (LKC) / PKR FAILED
 DST (3) 4317-47 (LKC) / PKR FAILED
 DST (4) 4314-47 (LKC) / 30-45-30-60, REC 10' M, W / SPTS
 OIL, SIP NA, FP 25-35#
 DST (5) 4340-72 (STARK SH) / 30-45-30-60, REC 30' SOCM, SIP
 1089-440#, FP 26-35 / 35-53#
 DST (6) 4608-4695 (MARM) / 30-45-45-60, REC 20' M, SIP 173-
 95#, FP 55-78 / 78-78#
 CORRECTION: 6/23/76 - ORIGINALLY FIRST REPORTED IN C SW
 SW

(over)

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

RECEIVED
 DEC 31 2002
 KCC WICHITA

15-193-20079-00-01

PRATHER OIL CORPORATION

#1-9 NOLETTE "OWWO"

9-10-33W
150' SW,

C SW SW

NEW INFO: FR 10/14/83, RE-ENTERED 11/15/83, WSH DWN TO 4488, SET 4 1/2 " 4488, MICT - CO, PF (LKC) 4352-58, AC 2000G (15%), SWB DWN, SO, NON-COMMERCIAL, SET BP AT 4346, PF (LKC) 4327-32 & 4310-14, ACIDIZED (AMT NA), SWB DWN, ALL PF'S COMMUNICATED, BAD CMT JOB, SQZ'D PFS W/CMT, RE-PF (LKC) 4327-32 & 4310-14, AC 3000G (15%), SWB DWN, GSO, POP, P APPX 20 BO & 10 BWPD

RECEIVED

DEC 31 2032

KCC WICHITA