

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20092-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 29-8S-19W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease Name: LOWRY B Well #: 2
County: ROOKS Total Vertical Depth: 3524 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 4.5 | 3454 | 0 | 300 SX |
| SURF | 8.625 | 245 | 0 | 170 SX |

114.53

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/24/2009 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 200# hulls - 10 sxs gel spacer.

Plugging Proposal Received By: BRUCE BASYE WitnessType: PARTIAL
Date/Time Plugging Completed: 02/24/2009 11:10 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3200' - spotted 40 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled to 2457' - spotted 10 sxs gel spacer.
Pulled to 1462' - pumped 105 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing - pumped 15 sxs 60/40 pozmix - 4% gel to top off 4 1/2" casing.
8 5/8" pressured to 500# immediately.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3259 | 3262 | | |

INVOICED

DATE 3-12-09
INV. NO. 2009061325

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 06 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: WELL ORGINALLY KNOWN AS LOWRY A-1. ALLIED CEMENTING COMPANY-TICKET #44223.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

Form CP-2/3

MAR 04 2009

PKT

RAINS & WILLIAMSON OIL CO. #1 LOWRY "A"


29--8--19W
SW NW NE

Contr. CO TOOLS

Cty. ROOKS

Geol. JAY DIRKS

Pool BRAY EXT



E. 2009 KB Cm. 1/7/68 Cp. 2/15/68 IP P 80 BOPD W/TR

GRAV 35/KC
3259½-62½

API 15-165-20,092

| LOG Tops | Depth | Datum |
|----------|-------|-------|
| TOP | 2961 | - 952 |
| GH | 3108 | -1099 |
| HEEB | 3164 | -1155 |
| TOR | 3188 | -1179 |
| LANS | 3202 | -1193 |
| BKC | 3408 | -1399 |
| CONG CHI | 3450 | -1441 |
| ARB | 3468 | -1459 |
| TD | 3524 | -1515 |
| | | |
| | | |
| | | |

Csg. 8" 245/170 SX, 4" 3454/300
DST 3167--96/70", WB, 25' MD O/S
BHP 175-42#/30", FP 23-37#
DST 3245-70/70", 65' HOCM, 60'
OCM, BHP 768--715#/30", FP 28--
79#
DST 3275-95/70", 1860' SW, BHP
1133-1133#/30", FP 95-977#
CO PF 3759½-62½, SWB 80 GMD&W, SWB
5 GOPH, NT, A 55 + A 250, SWB 3½
BFPH (95% O) FU 700' O/12 HRS, 6
2.92 80/30", ½ 80/30", 2 80/1 HR
A 2000, REC LD, SWB 5 BOPH, NW/
4 HRS, FU 700' FIH.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS