

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21801-00-00
Spot: S2NENW Sec/Twnshp/Rge: 29-8S-19W
4290 feet from S Section Line, 3300 feet from E Section Line
Lease Name: LOWRY Well #: B-3
County: ROOKS Total Vertical Depth: 3495 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		1475		400 SX
PROD	4.5	3494	0	100 SX
SURF	8.625	255	0	165 SX

113.59

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2009 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 200# hulls - 10 sxs gel spacer.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2009 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3200' - spotted 40 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 2457' - spotted 10 sxs gel spacer.
Pulled tubing to 1462' - pumped 100 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing - pumped 15 sxs 60/40 pozmix - 4% gel to top off 4 1/2" casing.
8 5/8" - pumped 15 sxs 60/40 pozmix - 4% gel - had 500# on backside.

Perfs:

Top	Bot	Thru	Comments
3450	3454		
3381	3384		
3284	3288		
3264	3268		
3208	3212		
2459	3461		

INVOICED
DATE 3-12-09
INV. NO. 2009061325

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 06 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: WELL ORIGINALLY KNOWN AS LOWRY B-1. ALLIED CEMENTING COMPANY-TICKET #44224.

Plugged through: TBG


District: 04

Signed Pat Bedore
(TECHNICIAN) CM

MAR 04 2009

PKT

RAINS & WILLIAMSON OIL CO., INC. #1 "B" LOWRY 29-8-19W
 435 PAGE COURT C S/2 NE NW
 WICHITA, KS 67202
 CONTR RAINS & WILLIAMSON OIL CTY ROOKS
 GEOL _____ FIELD BRAY
 E 2012 KB CM 9/27/82 ^{CARD} ISSUED 12/9/82 IP P 27 BOPD
 API 15-163-21,801 ARB 3460-3462



LOG	Tops	Depth/Datum
ANH	1558	454
TOP	2964	952
HEEB	3169	1157
LANS	3207	1195
BKC	3413	1401
ARB	3459	1447
RTD	3495	1483

8 5/8 " 255/165SX; 4 1/2 " 3494/100SX
 DST (1) 3256-3270 (LANS) / 30-30-30-30, REC 175' OIL SPKD
 MW, ISIP FAILED, FSIP 284#, FP 79-79 / 79-79#, BHT 107"
 DST (2) 3451-3460 (ARB) / 30-30-60-60, REC 20' CL OIL, 420'
 MO, ISIP FAILED, FSIP 1093#, FP 170-170 / 170-193#, BHT
 106"
 DST (3) 3452-3460 (ARB) / MISRUN, TOOL PLUGGED
 MICT - CO, PF (ARB) 3460-3462 W/4 SPF, AC 250G, SWB LD,
 R&T, POP, P 27 BOPD, 11/6/82

NOTE: ORIGINALLY FIRST REPORTED AS #3 LOWRY

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS