

KCC ACT Per
spot research
sent new

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20779-00-00

Spot: N2SE

Sec/Twnshp/Rge: 16-31S-17W

2230 feet from S Section Line, 1353 feet from E Section Line

Lease Name: FERRIN

Well #: 1-16

County: COMANCHE

Total Vertical Depth: 5100 feet

Operator License No.: 8061

String Size Depth (ft) Pulled (ft) Comments

Op Name: OIL PRODUCERS INC. OF KANSAS

PROD 4.5 5099 1640 WITH 125 SX CMT

Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

SURF 8.625 600

165.75

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 02/20/2009 8:30 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: BRANDON SIROKY

Company: OIL PRODUCERS

Phone: (316) 215-1357

Proposed Plugging Method: PUMP 200# HULLS & 30 SX CMT. PLUG AT 1040' WITH 12 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN

Witness Type: NONE

Date/Time Plugging Completed: 02/20/2009 1:30 PM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 200# HULLS & 30 SX CMT. TAGGED CMT @ 4910'. 1ST PLUG AT 1040' WITH 100# HULLS, 12 SX GEL, & 50 SX CMT. PIPE WAS STUCK. 2ND PLUG FREEPOINT PIPE @ 640'. PUMPED 100# HULLS & 50 SX CMT. 3RD PLUG AT 250' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5012	5030		

INVOICED

DATE 3-12-09

INV. NO. 2009061327

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 03 2009

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 01

RECEIVED

FEB 25 2009

KCC DODGE CITY

Signed

Eric MacLaren

(TECHNICIAN)

Form CP-2/3

[Handwritten initials]