

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20810-00-00
Spot: SENE Sec/Twnshp/Rge: 35-29S-40W
2100 feet from N Section Line, 700 feet from E Section Line
Lease Name: YASHELL SHIRIN Well #: 1-35
County: STANTON Total Vertical Depth: 5750 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4550		
PROD	4.5	5750	0	WITH 975 SX CMT
SURF	8.625	1552		WITH 610 SX CMT

186.88

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/05/2009 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUG AT 1580' WITH GEL WATER & 25 SX CMT. PLUG AT 600' CIRCULATE CMT TO SURFACE WITH 50 SX CMT. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2009 12:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 4550'. 1ST PLUG AT 1601' WITH 25 SX CMT. 2ND PLUG AT 630' WITH 38 SX CMT. NO CIRCULATION. STRONG VACUUM. TOOH W/ 20 JOINTS TBG. FILL 4 1/2" X 8 /58" ANNULUS WITH 17 SX CMT. PRESSURED TO 100 PSI. TAG CMT AT 960'. PUMP 50 SX CMT AT 600'. PRESSURED TO 400 PSI. CASING FULL.

Perfs:

Top	Bot	Thru	Comments
5609	5622		ST LOUIS

INVOICED
DATE 3-12-09
INV. NO. 2009061330

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 04 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

RECEIVED
FEB 19 2009
KCC DODGE CITY

Signed

Jack MacLashy
(TECHNICIAN)

Form CP-273