

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-21098-00-00
Spot: SWNWNWSE Sec/Twnshp/Rge: 21-29S-39W
2070 feet from S Section Line, 2311 feet from E Section Line
Lease Name: GAREY Well #: 6-J21-29-39
County: STANTON Total Vertical Depth: 5990 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5814		
PROD	5.5	5983	2323	WITH 190 SX CMT
SURF	8.625	1726		WITH 725 SX CMT

194.68

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2009 9:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT INTO PERFS. PLUG AT 1750' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2009 5:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 5814'. PUMP 200# HULLS & 25 SX CMT @ 5728'. 1ST PLUG AT 1750' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5824	5828		ST LOUIS
5728	5731		ST LOUIS

INVOICED
DATE 3-12-09
INV. NO. 2009061330
RECEIVED
KANSAS CORPORATION COMMISSION
MAR 04 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

RECEIVED
FEB 19 2009
KCC DODGE CITY

Signed Jack MacLaskey
(TECHNICIAN)