

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21424-00-02  
Spot: W2NWNese Sec/Twnshp/Rge: 1-33S-19W  
2310 feet from S Section Line, 1115 feet from E Section Line  
Lease Name: JACOB COLTER Well #: 2-1  
County: COMANCHE Total Vertical Depth: 5984 feet

Operator License No.: 33578  
Op Name: R J PATRICK OPERATING, LLC  
Address: PO BOX 1157  
LIBERAL, KS 67905

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	60		
PROD	4.5	5984	3860	WITH 200 SX CMT 194.48
SURF	8.625	675		WITH 375 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/25/2009 2:50 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: MARVIN T. MILLER Company: R.J. PATRICK OPERATING Phone: (620) 624-8483

Proposed Plugging Method: PUMP 200# HULLS & 30 SX CMT OR SAND TO 5850' & 4 SX CMT. PLUG AT 1080' WITH GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/25/2009 4:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 5840' & 4 SX CMT. 1ST PLUG AT 1080' WITH 100# HULLS, 15 SX GEL, & 50 SX CMT. 2ND PLUG AT 700' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 250' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5900	5902		
5898	5899		

INVOICED  
DATE 3-12-09  
INV. NO. 2009061332

KANSAS CORPORATION COMMISSION  
MAR 09 2009  
CONSERVATION DIVISION  
WICHITA KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED

MAR - 3 2009

KCC DODGE CITY

Signed Eric MacLaren  
(TECHNICIAN)