

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-00475-00-01  
Spot: SWSWNW Sec/Twnshp/Rge: 1-28S-13W  
3267 feet from S Section Line, 4783 feet from E Section Line  
Lease Name: HILLARD Well #: 1-A  
County: PRATT Total Vertical Depth: 2700 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2683	2026	WITH 100 SX CMT
SURF	8.625	364		WITH 350 SX CMT <b>87.75</b>

Well Type: SWD UIC Docket No: D14232.0 Date/Time to Plug: 02/18/2009 9:15 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 2390' & 5 SX CMT. PLUG AT 720' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/18/2009 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 2390' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PLUG THROUGH 5 1/2" CASING. 1ST PLUG AT 720' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2440	2600		

**INVOICED**  
DATE 3-12-09  
INV. NO. 2009061333

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 03 2009

CONSERVATION DIVISION  
WICHITA, KS

District: 01

RECEIVED  
FEB 25 2009  
KCC DODGE CITY

Signed Stephen J. Pfeifer  
(TECHNICIAN)

Form CR