

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12786-00-01
Spot: SWNESE Sec/Twnshp/Rge: 14-24S-14W
1692 feet from S Section Line, 1157 feet from E Section Line
Lease Name: MILLER Well #: 1-B
County: STAFFORD Total Vertical Depth: 3870 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3868	0	WITH 100 SX CMT
SURF	8.625	809		WITH 400 SX CMT <u>125.78</u>

Well Type: SWD UIC Docket No: D15066.0 Date/Time to Plug: 02/16/2009 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/16/2009 12:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

****CASING CEMENTED IN @ SURFACE* SANDED TO 3510' & 4 SX CMT.
PERFORATED 4 1/2" @ 830'. RAN TBG TO 837' & PUMPED 75 SX CMT PULLED
TBG. PUMPED 50 SX CMT DOWN 4 1/2" CASING. MAXIMUM PRESSURE 500 PSIG.
WELL ON VACUUM. WOC 30 MINUTES. PUMPED 30 SX CMT. WOC 1 HOUR.
PUMPED 30 SX CMT TO SURFACE.**

Perfs:

Top	Bot	Thru	Comments
3632	3642		

INVOICED
DATE 3-12-09
INV. NO. 2009061333

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 03 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

RECEIVED

FEB 25 2009

KCC DODGE CITY

Signed

Richard W. Lacey

(TECHNICIAN)

Form CP-2/3

[Signature]

PKT