

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-02061-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 20-24S-17E  
2475 feet from S Section Line, 5115 feet from E Section Line  
Lease Name: WILLE Well #: 1  
County: WOODSON Total Vertical Depth: 1242 feet

Operator License No.: 34047

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1231	0	
SURF	7	47	0	

Op Name: RON-BOB OIL LLC

40.37

Address: PO BOX 41  
NEOSHO FALLS, KS 66758

Well Type: EOR

UIC Docket No: E25042.1

Date/Time to Plug: 02/24/2009 9:00 AM

Plug Co. License No.: 33749

Plug Co. Name: KEPLEY WELL SERVICE, LLC

Proposal Rcvd. from: RON GERMAN

Company: RON-BOB OIL LLC

Phone: (623) 650-0919

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 1231' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 4 1/2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/24/2009 11:30 AM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 1230'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. APPROX. 117 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
1231	1242	CSG	

VOICED  
DATE 3-12-09  
INV NO. 2009061335

RECEIVED  
KCC DISTRICT #3

FEB 25 2009 CPT

CHANUTE, KS

RECEIVED  
MAR 2 2009  
KCC WICHITA

Remarks: SPOT LOCATION ESTABLISHED BY GPS AS 2595' NSL & 5229' WEL (VIA NAD 83).

Plugged through: TBG

District: 03

Signed Clayton P. Titel by SK  
(TECHNICIAN)

PLG