

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-21666-00-00
Spot: NW Sec/Twnshp/Rge: 20-24S-17E
660 feet from N Section Line, 330 feet from W Section Line
Lease Name: THOMAS WILLE Well #: 1
County: WOODSON Total Vertical Depth: 1238 feet

Operator License No.: 34047

Op Name: RON-BOB OIL LLC

Address: PO BOX 41
NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1238	0	
SURF	4.5	40		

40.24

Well Type: Oil

UIC Docket No:

Date/Time to Plug: 02/24/2009 11:30 PM

Plug Co. License No.: 33749

Plug Co. Name: KEPLEY WELL SERVICE, LLC

Proposal Recd. from: RON GERMAN

Company: RON-BOB OIL, LLC

Phone: (620) 650-0919

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 1238' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 02/24/2008 12:30 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 1230'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. APPROXIMATELY 110 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3

FEB 25 2009 CPT

CHANUTE, KS

INVOICED
DATE 3-12-09
INV NO. 2009061335

RECEIVED
MAR 12 2009

KCC WICHITA

Remarks: SPOT LOCATION ESTABLISHED BY GPS AS 2097' NSL & 2595' WEL (VIA NAD 83)

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PT