

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23107-00-00
Spot: SWSESE Sec/Twnshp/Rge: 18-33S-12W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: BARTHOLOW Well #: 2-18
County: BARBER Total Vertical Depth: 4950 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 200 W DOUGLAS AVE STE 520
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4615	3800	WITH 100 SX CMT
SURF	8.625	311		WITH 190 SX CMT

100.88

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/20/2009 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4450' WITH 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 02/20/2009 2:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND BACK TO 4450' & 5 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4503	4520		

INVOICED
DATE 3-12-09
INV. NO. 2009061B37

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 03 2009

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

RECEIVED

FEB 25 2009

KCC DODGE CITY

Signed

Eric MacLaren

(TECHNICIAN)

Form CP-2/3