

15-195-20868-00-00 9-27

6 041072

API NUMBER 15- 195-20,868

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW SW, SEC. 11, T 11 S, R 22 W/EX

1650 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Kramer Well # 1

Operator: John O. Farmer Inc.

County Trego 124.96

Name & Address Box 352

Well Total Depth 3845 feet

Russell, Ks. 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 222' w/180 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Russell, Ks.

Company to plug at: Hour: 10:00 Day: 9 Month: 27 Year: 19 89

Plugging proposal received from Lawrence Slim Eichman

(company name) J. O. Farmer (phone)

were: 4 1/2" casing set at 3841' w/125 sks. Ran tubing to 2100' perf tubing

and casing at 1615' and base dakota at 725'.

Ordered 400 sks 65/35 poz 10% gel w/1/4# f.c. plus 6 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:45 PM Day: 27 9 Month: 27 9 Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 2100' tubing hanging up: Perf anhy at 1615' and perf base dakota at 775': Pumped and circ 200 sks cement from 2100' to surface: Pulled tubing, 18 joints, 49 joints left in hole: Sq. add 100 sks cement in casing: Hooked up to 8 5/8" s.p. Pumped 100 sks cement w/3 sks hulls in cement. Max psi 800# Shut in 400#.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED

Signed Dennis L. Hamel (TECHNICIAN)

DATE 10-25-89

INV. NO. 26217