

10-315-195-21501-00-00

6 031287

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
NE NE SE, SEC. 11, T. 11s, R. 22 W/EK
2310 feet from S section line
330 feet from E section line
Lease Name Kramer Well # 1-B
County Trego 125.45
Well Total Depth 3860 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 304

TECHNICIAN'S PLUGGING REPORT
Operator License # 4767
Operator: Ritchie Exploration Inc.
Name & Address: 125 N. Market #1000
Wichita, Ks. 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Ks. 67524

Company to plug at: Hour: PM Day: 3 Month: October Year: 19 89

Plugging proposal received from Millard

(company name) Kelso (phone)

were: 8 5/8 set at 304' w/200 sks. 4 1/2" set at 3859' w/100 sks. Perf 3759' - 69'.

Order sand and cement. Pull pipe. Order 225 sks 65/35 poz 10% gel 500# hulls.

Allied Cement Co. Rush water trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00 PM Day: 3 Month: October Year: 19 89

ACTUAL PLUGGING REPORT Sand bottom to 3710 w/ 4 sks common cement on sand on bailer.

One shot recovered 2400' of 4 1/2" casing. Squeezed 8 5/8" w/225 sks

cement blend to max psi 1100#. Close in psi 500#. Plug completed.

STATE RECEIVED
OCT 20 1989
10-20-1989

Remarks: (If additional description is necessary, use BACK of this form.)

INVOTCED observe this plugging.

DATE 10-25-89

INV. NO. 26237

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow