

15-195-20991-00-00
5-1

To: **6 031359**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SW SW SE, SEC. 12, T. 11 S, R. 22 W/EX

330 feet from S section line
2310 feet from E section line

Lease Name Fowler Well # 1
County Trego 126.13

Well Total Depth 3881 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 230' w/160

TECHNICIAN'S PLUGGING REPORT
Operator License # 4424

Operator: Smokey Valley Res.

Name & Address George Sailing

Box 165 McPherson, Ks. 67460

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number _____

Address Chase, Ks.

Company to plug at: Hour: _____ PM Day: 1 Month: May Year: 19 90

Plugging proposal received from Bill

(company name) Kelso (phone) _____

were: 8 5/8 set at 230 w/160 sks. 4 1/2 set at 3878 w/ sks.

Perf 3774 - 84. Order sand and common cement. Pull pipe. Order 225 sks

65/35-poz 10% gel 2% dicel 500# hulls. Allied Cement Co. Wellbrock.

Plugging Proposal Received by Carl (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45PM Day: 1 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Sand to 3725 w/4 sks common cement on sand w/
bailer. Recovered 1050. Sq 8 5/8 w/225 sks 500# hulls to 800 max psi. Close in psi

150#. Plug complete.

Remarks: _____

INVOICED (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 5-16-90 5-7-1990
INV. NO. 28172
5-1

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow