

5-16 15-195-21442-00-00

6 031248

API NUMBER 15- 195-21,442-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW SW NW, SEC. 12, T 11 S, R 22 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Lease Name McConkey Well # A-1

Operator: Davis Petroleum Inc.

County Trego 124.64

Name & Address: Route 1 Box 183 B

Well Total Depth 3835 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 16 Month: May Year: 19 89

Plugging proposal received from Clay

(company name) Kelso (phone)

were: 8 5/8" set at 293' w/210 sks cwc. 4 1/2" set at 3832' w/200 sks PBDT 3807'.

Perfs at 3756' - 68'. Order sand and common cement. Pull pipe, order 200 sks 65/35 Poz 10% Gel 2% Dicol 500# Hulls. Allied Cement Co. Rush Water Trucks.

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1989
6-6-1989

Plugging Proposal Received by Carl Goodrow

(TECHNICIAN)

Plugging Operations Completed by Agent?: All Part None

Operations Completed: Hour: 2:00PM Day: 16 Month: May Year: 19 89

ACTUAL PLUGGING REPORT

Sand bottom to 3700' w/4 sks common cement on sand w/bailer. One shot recovered 2500' of 4 1/2" pipe. Squeezed 8 5/8" w/200 sks cement blend w/400# Hulls to max psi 800#. Close in psi 300#. Plug complete. Very tight hole. Bottom plugs from office.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
Reserve this plugging.

Jub.S.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

DATE 6-7-89

INV. NO. 25000