

9-19

4-041930 15-195-21523-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-195-21,523-00-00

C SE NW /4 SEC. 20, 11 S, 22 W  
1980 feet from S section line  
1980 feet from E section line

Operator license# 9559

Lease: Nilhas Well # 1

Operator: Jerry Patterson Oil

County: Trego 129.42

Address: P.O. Box 307  
Logan, Kansas 67646

Well total depth 3982 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 208 Feet  
W/N/A sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 19 Month: September Year 1997

Plugging proposal received from: Jerry Patterson

Company: Jerry Patterson Oil Phone: -

Were: 4 1/2" casing set at 3981' w/150 sxs cement.  
Perfs at 3874' - 3878'. Anhy at 1750'. Dakota at 900'. W.L.M. at 3880'. T.O.F. at 2000'.  
Ordered 140 sxs Halliburton Mid Con #2 cement with 1/4# F.C. plus 500# hulls and 16 sxs gel.

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 1:00 P.M., Day: 19, Month: September, Year: 1997

Actual plugging report: Squeezed in 4 1/2" 16 sxs cement with 200# hulls and (32 bbls.)  
followed with 16 sxs gel, followed with 100 sxs mid-con with 200# hulls. Max. P.S.I. 450#.  
Squeezed down 8 5/8" S.P. 24 sxs mid-con with 1/4# F.C. S.I.P. 200#.

Remarks:  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING, CASING X  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO  
Elevation: G.L.

I did[ X ] / did not[ ] observe the plugging.

*Dennis L Hamel*  
(agent)

Form CP-2/3

INVOICED

Lbb1-52-b

DATE SEP 26 1997

INV. NO. 49164

9-19