

15-195-20730-00-00
6-070946

180
K

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-20,730-00-00
NE NE SW /4 SEC. 20, 11 S, 22 W
2310 feet from S section line
2970 feet from E section line

Operator license# 8572 Lease Nilhas well # 1-A

Operator: Reach Oil Corporation County Trego

Address: d/b/a The Reach Group Well total depth 4020 feet 130.65
229 E. William #500 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 247 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License#

Address: 1707 East 10th Street, Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 4th Month: September Year: 91

Plugging proposal received from: Earl Ringeisen

Company: Reach Oil Corporation Phone: 316-262-1522

Were: 8 5/8" 247' S.P. cvc. w/175 sx. cement. 4 1/2" casing set
@ 4014' w/300 sx. cement. 4 1/2" casing perf. @ 1184' cvc. w/170 sx.
Perf. @ 3893' to 3654'. Proposal 275 sx. 65/35 pozmix - 8% gel. -
5 sx. hulls. Load both 4 1/2" casing and 4 1/2" x 8 5/8" annulus with
cement. Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All], Part], None]

Completed: Hour: 2:30P.M., Day: 4th, Month: September, Year: 91

Actual plugging report: Reach Group ordered 275 sx. 65/35 poz. -
8% gel. - 5 sx. hulls. Pumped in with pump truck. 1) Pressured
annulus w/5 sx. cement. Max. pressure 400 P.S.I. Shut in 400 P.S.I.
2) Pumped in 4 1/2" casing w/15 sx. cement followed w/185 sx. cement
w/5 sx. hulls. Max. pressure 900 P.S.I. Shut in @ 600 P.S.I.
Cemented by B.J. Services, Hays, Kansas.

RECEIVED
COMMISSION

Remarks:
OCT 01 1991
10-1-1991
DIVISION
KANSAS

I do] observe the plugging.

Marion J. Schmidt

(agent)
Form CP-2/3

INVOICED
DATE 10-28-91
INV. NO. 33493

9-4 NOV 20 1991