

15-195-20598-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20598-00-00
Spot: CE2SESE Sec/Twnshp/Rge: 20-11S-22W
660 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: UHRICH Well Number: 1
County: TREGO Total Vertical Depth: 4030 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 243 w/180 sxs cmt
Production: Size 4.5 feet: 4020 w/150 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/20/2002 9:00 AM
Plug Co. License No.: 32579 Plug Co. Name: PFEIFER DOZER SERVICE, LLC
Proposal Rcvd. from: LEON PFEIFER Company: PFEIFER DOZER SERVICE, LLC Phone: (785) 627-5711

Proposed Plugging Method: According to KCC Rules and Regulations.
Ordered 250 sxs cement with 600# hulls.
Perfs at 775' - 1825' - 2300'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/20/2002 2:15 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. to 243' w/180 sxs cement. 4 1/2" casing to 4020' w/150 sxs cement.
Ran sand line to 3000'.
Ran tubing to 2325'. Spotted 100 sxs with 500# hulls.
Pulled to 1150' and circulated with 30 sxs cement and 100# hulls.
Max. P.S.I. 800#. S.I.P. 400#.
Tied to 8 5/8" x 4 1/2" annulus and squeezed 40 sxs to Max. P.S.I. 500#. S.I.P. 200#.
Total of 170 sxs 60/40 pozmix - 10% gel and 600# hulls.

RECEIVED
FEB 28 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. PFEIFER WELL SERVICE-WATER.

Plugged through: TBG

District: 04

Signed Roger L. Moses
(TECHNICIAN)

107

FEB 26 2002

F & M OIL CO., INC
 505 UNION CENTER
 WICHITA, KS 67202
 CONTR ABERCROMBIE DRILLING CTY TREGO

#1 UHRICH
 20-11-22W
 C E/2 SE SE

GEOL NEIL SIKES FIELD SHAW CREEK EXT (1/4 W)

E 2342 KB CM 11/10/76 ^{CARD} ISSUED 4/3/80 IP P 11.97 BOPD &
 TR WTR
 MARM 3946-3973 OA

API 15-195-20,598

LOG	TOPS	DEPTH	DATUM
ANH		1794	± 548
TOP		3202	- 860
HEEB		3576	-1234
TOR		3598	-1256
LANS		3613	-1271
B KC		3848	-1506
MARM		3944	-1602
ARB		4016	-1674
PSTD		3982	-1540
RTO		4025	-1683
LTD		4030	-1688

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

	+	+	+
	+	+	+
	+	+	+

8-5/8" 243/180sx, 4 1/2" 4020/150sx

DST (1) 3636-60/30-30-30-30, REC 20'
 M, SIP 823-815#, FP 31-55#

DST (2) 3580-3660 (W/SP)/30-30-60-45,
 REC 195' O SPKE M W/SO IN TOOL,
 SIP 957-870#, FP 94-172#

DST (3) 3658-3702/30-45-60-45, REC 50'
 M, 550' MDY W, SIP 862-831#, FP
 55-314#

DST (4) 3736-3822/30-30-30-30, 5'M,
 SIP 70-70#, FP 62-62#

DST (5) 3936-72/30-45-60-45, REC 180'
 GIP, 90' VHOCM, 240' MDY O, SIP
 1135-1026#, FP 47-157#

DST (6) INTERVAL UNKNOWN/MISRUN
 (OVER)