

6070507

API NUMBER 15-195-21,249-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW-NW-JW, SEC. 14, T 11 S, R 22 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5226  
Operator: Quinn Oil Prod. Inc.  
Name & Address: P.O. Box 684  
Hays, Kans. 67601  
Glenn Diehl

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

Lease Name Lynd Well # 1  
County Trego 128.38  
Well Total Depth 3950 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B.J. Titon License Number \_\_\_\_\_  
Address South Canterbury Hays, Kans. 67601

Company to plug at: Hour: 2:00 PM Day: 10<sup>th</sup> Month: Sept. Year: 19 86

Plugging proposal received from Glenn Diehl

(company name) Quinn Oil Production, Inc (phone) 913-625-2106

were: 8 5/8" - 249' SP. CUC<sup>11</sup> / 175' <sup>SK</sup>ent, 4 1/2" Csg. Set @ 3949' <sup>12</sup>ent.  
Top Stage Cemented <sup>11</sup>425' <sup>SK</sup>, 1700' <sup>15</sup>to Surface, Plug Back 2913' <sup>12</sup>ent.  
Csgs @ 2863-68' <sup>15</sup>, 2871-75' no pipe Recovery, Proposal, Order  
125' <sup>15</sup>Econolite <sup>65</sup> / 25' <sup>10</sup>Formix <sup>10</sup> Gel - 2' <sup>10</sup>additive and 6' <sup>15</sup>shells, Pump Cement in  
annulus and Pressure, Pump and load 4 1/2" csg<sup>11</sup> / cement and  
pressure. Plugging Proposal Received by Marion Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:00 PM Day: 10<sup>th</sup> Month: Sept. Year: 19 86

ACTUAL PLUGGING REPORT Ordered 125' <sup>15</sup>SK <sup>65</sup> / 25' <sup>10</sup>Formix 10% Gel, 2% <sup>10</sup>additive, and 6' <sup>15</sup>SK shells.

Pumped in Annulus between 4 1/2" Csg and 8 5/8" SP.  
110' <sup>15</sup>SK ent, max. Pressure 600 Psi.g (annulus was <sup>11</sup>425' <sup>15</sup>SK)

Pumped in 4 1/2" csg. 10' <sup>15</sup>SK ent, 3' <sup>15</sup>SK shells, then 115' <sup>15</sup>SK ent  
max pressure 1500 Psi.g - Csg Shut in @ 1300 Psi.g.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (I, did, did not) observe this plugging.

DATE 9-17-86 also Witnessed by \_\_\_\_\_

Signed Marion Schmidt  
(TECHNICIAN)

INV. NO. 14970 Dee Batthay 9-15