

15-195-20968-00-00

4-071145

SEP 26 1995
9-261995

API Number: 15-195-20,968-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NW NE SE /4 SEC. 17, 11 S, 22 W
2310 feet from S section line
990 feet from E section line

Operator license# 4767

Lease: Baughman "D" Well # 1

Operator: Ritchie Exploration, Inc.

County: Trego 127.47

Address: 125 N. Market - #1000
Wichita, Kansas 67202
John Niernberger

Well total depth 3922 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 167 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 26 Month: September Year: 1995

Plugging proposal received from: Pete Forine

Company: Ritchie Exploration, Inc. Phone: 316-267-4375

Were: 8 5/8" - 167' S.P. cwc. w/145 sxs cement. 4 1/2" casing set at 3916' w/175 sxs cement. 4 1/2" casing squeeze at 1050' w/200 sxs cement. Static fluid at 2900'. Perfs. at 3472' to 3810'. Elv. at 2201' - Anhy. at 1663' - T.D. 3922'. Proposal perforate 4 1/2" casing at 1680' - 825'. Order 350 sxs 60/40 pozmix - 8% gel - 500# of cotton seed hulls. Pump in with pump truck. Pump in 4 1/2" casing w/15 sxs cement, followed with enough cement to fill 4 1/2" casing top to T.D. Squeeze 4 1/2" x 8 5/8" annulus with cement pressure to 300 P.S.I.

RECEIVED
STATE CORPORATION COMMISSION

10-6-1995
OCT 6 1995

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All [X], Part [], None []

CONSERVATION DIVISION
Wichita, Kansas

Completed: Hour: 10:35 A.M., Day: 26, Month: September, Year: 1995

Actual plugging report: Ritchie Exploration ordered 350 sxs 60/40 pozmix - 8% gel - 5 sxs. hulls. Pumped in 4 1/2" casing with pump truck.

1. Fluid at 2900'.
2. Perforated 4 1/2" casing at 1680' and 825' (Mercury Wireline).
3. Pumped in 4 1/2" casing with 20 sxs cement followed with 220 sxs cement with 4 sxs hulls. Max. P.S.I. 700# - S.I.P. 400#.
4. Squeezed 4 1/2" x 8 5/8" annulus with 45 sxs cement. Max. P.S.I. 700#. S.I.P. 400#.

Remarks: Cemented by Allied Cementing - Russell, Kansas 67665
Condition of casing(in hole): GOOD X BAD
Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: 2201 GL

I did [] / did not [] observe the plugging.

Marion J. Schmidt
(agent)

Form CP-2/3

INVOICED

DATE OCT 10 1995

INV. NO. 43721

HTD