

15-195-20796-00-00

4-031936

5-31

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-20,796-00-00

SE NE NW /4 SEC. 17, 11 S, 22 W
4290 feet from S section line
2970 feet from E section line

Operator license# 4767 Lease Lloyd Nilhas "B" well # 2

Operator: Ritchie Exploration, Inc. County Trego

Address: 125 N. Market Well total depth 3890 feet
Suite 1000 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 176 feet

126.42

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 31 Month: May Year: 94

Plugging proposal received from: John

Company: Ritchie Exploration, Inc. Phone:

Were: Order 250 sxs. 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 9:30A.M., Day: 31, Month: May, Year: 94

Actual plugging report: 8 5/8" set @ 176' w/160 sxs. cwc. 4 1/2" set @ 3886' w/150 sxs. P.B.T.D. 3797'. Prod. Perf. 3315' - 3810'. Squeezed w/200 sxs. at 1140'. Casing bad 900' to 2200'. Pulled rods and tubing - low fluid level. Mix and pumped down 4 1/2" w/200 sxs. cement blend with 500# hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 1000#. Squeezed 8 5/8" w/50 sxs. cement blend to Max. P.S.I. 200#. Close in P.S.I. 200#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD ~~X~~ BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] / did not [] observe the plugging. RECEIVED Carl Goodrow

DATE 6-16-94
INV. NO. 40573

JUN 15 1994
6-15-1994
(agent)
Form CP-2/3
CONSERVATION DIVISION
Wichita, Kansas