

**ORIGINAL**

**WELL COMPLETION FORM**

**WELL HISTORY - DESCRIPTION OF WELL & LEASE**

Operator: License # 32309  
Name: Presco Western, LLC  
Address 5665 FLATIRON PARKWAY  
City/State/Zip BOULDER CO 80301  
Purchaser: High Sierra Crude (oil)/BP (gas)  
Operator Contact Person: Randy M. Verret  
Phone ( 303 ) 305-1163  
Contractor: Name: Trinidad Drilling  
License: 33784  
Wellsite Geologist: not applicable

API NO. 15- 081-21720-0000  
County Haskell  
SE - NW - SE - NW Sec. 30 Twp. 30 S. R. 33  E  W  
1,746 Feet from S(N) (circle one) Line of Section  
1,670 Feet from EW (circle one) Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE NW SW  
Lease Name SWLVLU Well # I17  
Field Name Victory

Designate Type of Completion  
 New Well  Re-Entry  Workover  
 Oil  SWD  SIOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc.)

Producing Formation Lansing  
Elevation: Ground 2,958' Kelley Bushing 2,970'  
Total Depth 4,400' Plug Back Total Depth \_\_\_\_\_  
Amount of Surface Pipe Set and Cemented at 1,755 Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set 3,273 Feet  
If Alternate II completion, cement circulated from \_\_\_\_\_  
feet depth to AKI-Verret sx cmt.


If Workover/Reentry: Old Well Info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Original Comp. Date \_\_\_\_\_ Original Total Depth \_\_\_\_\_  
 Deepening  Re-perf.  Conv. to Enhr./SWD  
 Plug Back \_\_\_\_\_ Plug Back Total Depth \_\_\_\_\_  
 Commingled Docket No. \_\_\_\_\_  
 Dual Completion Docket No. \_\_\_\_\_  
 Other (SWD or Enhr?) Docket No. \_\_\_\_\_  
07/23/2007 8/01/2007 9/28/2007  
Spud Date or Date Reached TD Completion Date or Recompletion Date

Drilling Fluid Management Plan  
(Data must be collected from the Reserve Pit)  
Chloride content 7,500 ppm Fluid volume 1000 bbls  
Dewatering method used Air Evaporation  
Location of fluid disposal if hauled offsite: \_\_\_\_\_  
Operator Name \_\_\_\_\_  
Lease Name \_\_\_\_\_ License No. \_\_\_\_\_  
Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  E  W  
County \_\_\_\_\_ Docket No. \_\_\_\_\_

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature [Signature]  
Title Manager - Business & Regulatory Affairs Date 01/08/2008  
Subscribed and sworn to before me this 16th day of January  
20 08  
Notary Public [Signature]  
Date Commission Expires 2-12-2011 My Commission Expires 02/12/2011



KCC Office Use ONLY **RECEIVED**  
KANSAS CORPORATION COMMISSION  
 Letter of Confidentiality Attached  
If Denied, Yes  Date: **JAN 17 2008**  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution  
WICHITA, KS

Operator Name Presco Western, LLC

Lease Name SWLVLJ

Well # I17

Sec. 30 Twp. 30 S.R. 33  East  West

County Haskell

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets.)	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datums <input type="checkbox"/> Sample Name                      Top                      Datum Heebner                      4,000'                      -1,030' Lansing                      4,098'                      -1,128'
Samples Sent to Geological Survey	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
Cores Taken	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Electric Log Run (Submit Copy.)	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
List All E.Logs Run: Porosity, Cement Bond Log		

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4"	8 5/8"	23.0	1,755'	65/35/C1 C	575/150	6&3%OC/1/4FloSea
Production	6 1/4"	4 1/2"	10.5	4,399'	Lite/ASC	50/50	1/4flo seal/2%gel
					Lite	300	1/4 flo seal

ADDITIONAL CEMENTING/SQUEEZE RECORD				
Purpose	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
Perforate				
Protect Casing				
Plug Back TD				
Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4,098 - 4,108' (Lansing)	24 bbls acid/30 bbls flush	
4	4,118 - 4,124' (Lansing)		

TUBING RECORD		Size 2 7/8"	Set At 4,371'	Packer At	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumed Production, SWD or Enhr. 9/28/2007			Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls. 62	Gas Mcf -0-	Water Bbls. -0-	Gas-Oil-Ratio -0-	Gravity 37.5

Disposition of Gas:                      METHOD OF COMPLETION                      Production Interval

Vented     Sold     Used on Lease     Open Hole     Perforation     Dually Comp.     Commingled

(If vented, submit ACO-18.)                       Other (Specify) \_\_\_\_\_

# ALLIED CEMENTING CO., INC.

31138

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
MEDICINE LODGE

DATE <u>7-25-07</u>	SEC. <u>30</u>	TWP. <u>30 S</u>	RANGE <u>33 W</u>	CALLED OUT <u>10:30 am</u>	ON LOCATION <u>3:45 pm</u>	JOB START <u>6:45 pm</u>	JOB FINISH <u>9:50 pm</u>
LEASE <u>SN/1010</u>	WELL # <u>I-17</u>		LOCATION <u>SAPTANTA, KS, EAST EDGE, 1/2 S, HASKELL</u>		COUNTY <u>KS</u>	STATE <u>KS</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)			ON HWY 190, 1/2 E, 1/3 S, WINTO				

CONTRACTOR X-TREME #1  
 TYPE OF JOB SURFACE CASING  
 HOLE SIZE 12 1/4" T.D. 1,755'  
 CASING SIZE 8 5/8" DEPTH 1,755'  
 TUBING SIZE DEPTH  
 DRILL PIPE DEPTH  
 TOOL DEPTH  
 PRES. MAX 1,100 MINIMUM 100  
 MEAS. LINE SHOE JOINT 40.53'  
 CEMENT LEFT IN CSG. 40.53'

OWNER PRESKO WESTERN  
 CEMENT  
 AMOUNT ORDERED 575 SK 65.25% L + 39 SK CC + 14" FLO SEAL, 150 SK CLASS C + 39 SK CC

PERFS.  
 DISPLACEMENT 112 1/2 bbl. FRESH WATER

COMMON	<u>150 C.</u>	@	<u>15.40</u>	<u>2310.00</u>
POZMIX		@		
GEL		@		
CHLORIDE	<u>24</u>	@	<u>46.60</u>	<u>1118.40</u>
ASC		@		
	<u>575 A-LW</u>	@	<u>11.85</u>	<u>6813.75</u>
	<u>FLO SEAL 144"</u>	@	<u>2.00</u>	<u>288.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>785</u>	@	<u>1.90</u>	<u>1491.50</u>
MILEAGE	<u>30 x 785 x .09</u>			<u>219.50</u>
TOTAL				<u>14141.5</u>

EQUIPMENT  
 PUMP TRUCK CEMENTER BILL M.  
 # 360 HELPER ROBERT H.  
 BULK TRUCK  
 # 355 DRIVER KANDY F.  
 BULK TRUCK  
 # 381 DRIVER RAYMOND K.

REMARKS:

PIPE ON BOTTOM, BREAK CIRCULATION,  
PUMP PLS. FLUSH, PUMP 575 SK 65.25% L  
+ 39 SK CC + 14" FLO SEAL, 150 SK CLASS C  
+ 39 SK CC, STOP PUMPS, RELEASE PLUG,  
START DISPLACEMENT, SEE LIST, SLOW  
RATE PUMP PLUG, FLOAT HEAD,  
DISPLACED WITH 112 1/2 bbl. FRESH  
WATER, CIRCULATE CEMENT.

SERVICE

DEPTH OF JOB	<u>1,755'</u>		
PUMP TRUCK CHARGE			<u>1610.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>30</u>	@	<u>6.00</u> <u>180.00</u>
MANIFOLD <u>HEAD RENT</u>		@	<u>100.00</u> <u>100.00</u>
		@	
		@	
TOTAL <u>1890.00</u>			

CHARGE TO: PRESKO WESTERN

STREET


CITY

AP Approval Stamp - Drilling Well	
Well Name	<u>SAPTANTA I-17</u>
Company	<u>Presko Western, LLC - 700</u>
Coat Center	
AFE	<u>07073KS</u>
Approval	
GL Code	<u>4000 / REC 0100 / TE 0200 / 160</u>

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE



PLUG & FLOAT EQUIPMENT

<u>8 1/2" RUBBER PLUG</u>	<u>1</u>	@	<u>100.00</u>	<u>100.00</u>
<u>8 1/2" SURFACE COLLAR</u>	<u>1</u>	@	<u>600.00</u>	<u>600.00</u>
<u>8 1/2" CONTRAILOR</u>	<u>10</u>	@	<u>55.00</u>	<u>550.00</u>
<u>8 1/2" ADHESIT</u>	<u>1</u>	@	<u>220.00</u>	<u>220.00</u>
<u>8 1/2" GUIDE SLEEVE</u>	<u>1</u>	@	<u>250.00</u>	<u>250.00</u>

TOTAL 1720.00

TAX - 0 -

TOTAL CHARGE

DISCOUNT

IF PAID IN 30 DAYS

RECEIVED  
KANSAS CORPORATION COMMISSION

JAMES TEFF

PRINTED NAME

JAN 17 2008

CONSERVATION DIVISION  
WICHITA KS

# ALLIED CEMENTING CO., INC.

28680

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Orville, Mo

DATE 8-1-07	SEC. 20	TWP. 30S	RANGE 33W	CALLED OUT	ON LOCATION 6:30 AM	JOB START 11:00 AM	JOB FINISH 12:00 PM
LEASE SWLVLV	WELL # 1-17	LOCATION Atlanta 1 1/2 S 1/2 E			COUNTY Mackall	STATE MO	
OLD OR NEW (Circle one) <u>NEW</u>				S S win			

CONTRACTOR X-treme #1  
 TYPE OF JOB 2-stage (Top)  
 HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_  
 CASING SIZE 4 1/2 I.D. 10.5 DEPTH 3273  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT 52.01 PAKS

OWNER same  
 CEMENT  
 AMOUNT ORDERED 300 lbs 1 1/4"  
Classical

RECEIVED  
KANSAS CORPORATION COMMISSION

COMMON \_\_\_\_\_ @ \_\_\_\_\_  
 POZMIX \_\_\_\_\_ @ JAN 17 2008  
 GEL \_\_\_\_\_ @ \_\_\_\_\_  
 CHLORIDE \_\_\_\_\_ @ \_\_\_\_\_  
 ASC \_\_\_\_\_ @ \_\_\_\_\_  
 L 4 e 300 @ 11.25 3375.00  
 Classical 75 @ 2.00 150.00  
 HANDLING 324 @ 1.70 615.60  
 MILEAGE .09 x 54 mi @ 1.00 874.90  
 TOTAL 5015.40

EQUIPMENT

PUMP TRUCK CEMENTER Terry May  
 # 417 HELPER Wally  
 BULK TRUCK  
 # 304 DRIVER Jerry  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

Mix 300 lbs 1 1/4" Classical  
wash out pump & lines  
Displace plus to DU Tool  
lift pump 1000# hand pump 1200#  
Tool closed cement circ  
Approx 5 BRL. Plus down  
@ 11:30 AM  
Thanks Terry &  
crew

SERVICE

DEPTH OF JOB \_\_\_\_\_  
 PUMP TRUCK CHARGE \_\_\_\_\_ 955.00  
 EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_  
 MILEAGE \_\_\_\_\_ @ \_\_\_\_\_ NA  
 MANIFOLD 1 hand @ \_\_\_\_\_ 100.00  
 L 4 e 1.98-12.4-10.88  
 TOTAL 1055.00

CHARGE TO: Progro-Workman LLC  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE SWLVLV MO ZIP \_\_\_\_\_

PLUG & FLOAT EQUIPMENT

\_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME

# ALLIED CEMENTING CO., INC.

28679

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

OAKLEY, KS

DATE 7-31-07	SEC. 30	TWP. 30S	RANGE 33W	CALLED OUT	ON LOCATION 1:00 AM	JOB START 5:30 AM	JOB FINISH 6:30 AM
LEASE SW LULU	WELL # 1-17	LOCATION S-24-T-112S-12E			COUNTY Washell	STATE KS	
OLD OR NEW (Circle one)				112S W-11			

CONTRACTOR <del>...</del> V-trome #1	OWNER same
TYPE OF JOB 2-stage bottom stage	
HOLE SIZE 6 1/4" T.D.	CEMENT
CASING SIZE 4 1/2" 10.5 DEPTH 11399'	AMOUNT ORDERED 50 sacks Lile 114# salt 50 sacks ASC 29# salt, 10% salt 5# salt 31.6% salt 1 lb salt
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL JOI -	DEPTH 3273'
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT 40'
CEMENT LEFT IN CSG.	40'
PERFS.	
DISPLACEMENT 69,317 gals	

**EQUIPMENT**

PUMP TRUCK # 417	CEMENTER Tuzza Max
BULK TRUCK # 394	HELPER Kelly
BULK TRUCK # 377	DRIVER Jerry
BULK TRUCK # 377	DRIVER Rex

**REMARKS:**

min 50 sts Lile 114# salt  
Tubing with 50 sacks ASC @ 29#  
10% salt, 5# salt 31.6% salt 1 lb salt  
check out pump & lines Displace  
plus to breakdown Lile press  
500# hand pipe 1000#  
breakdown hold pipe down @ 30g  
breakdown Displace with 15 mins  
open DU tool @ 2000' circulate  
4 hrs

CHARGE TO: Proser Washell LLC  
STREET \_\_\_\_\_  
CITY \_\_\_\_\_ STATES WASHELL I-17 ZIP \_\_\_\_\_

COMMON	@		
POZMIX	@		
GEL	@	1	16.65
CHLORIDE	@		
ASC	@	50 sacks	14.00
Lile	@	50 sacks	11.25
SALT	@	3 cut	19.20
G. Limestone	@	250#	.70
CB-31	@	24#	7.20
D-Connex	@	12#	7.20
Cl-5 seal	@	13#	2.92
HANDLING	@	120	1.92
MILEAGE	@	max 4 mile	32.40
ASC - 1.57		14.41	6.90
Lile - 1.98		12.41	10.98
<b>TOTAL</b>			<b>2401.75</b>

**SERVICE**

DEPTH OF JOB	4399'
PUMP TRUCK CHARGE	1675.00
EXTRA FOOTAGE	@
MILEAGE	30 @ 6.00 = 180.00
MANIFOLD + head	@ 100.00
THANKS	@
<b>TOTAL</b>	<b>1955.00</b>

5 1/2" hole

6. Centralizer	45.00	270.00
1. Float shoe	@	385.00
1. Breakdown Assy	@ (Flow)	360.00
1. DU Tool	@	3750.00
1. Reg Centralizer	@	45.00
<b>TOTAL</b>		<b>4810.00</b>

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION  
TAX

TOTAL CHARGE JAN 17 2008

DISCOUNT CONSERVATION DIVISION WICHITA, KS IF PAID IN 30 DAYS

PRINTED NAME \_\_\_\_\_