

FED ID# 48-1214033
 MC ID# 158212
 Shop # 820 437-2661
 Cellular # 820 437-7582
 Office # 316 685-5908
 Office Fax # 316-685-5928
 Shop Address: 3813A Y Road
 Madison, KS 66860

Hurricane Truck Services, Inc.
 P.O. Box 782228
 Wichita, KS 67278-2228

Cement and Acid
 Service Ticket
 T 1870

DATE 5-23-07

COUNTY BOHCO CITY _____

CHARGE TO Running Foxes

ADDRESS _____ CITY _____ ST _____ ZIP _____

LEASE & WELL NO. VOGEL 15-36B CONTRACTOR _____

KIND OF JOB Long string SEC. _____ TWP. _____ RNG. _____

DIR. TO LOC. 2nd Job OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
			700.00
65 SKS	Quick-Set cement (8" Gyp-seal, 22 ACCL, 2% Gel)	13.82	898.30
260 lbs	KOL-SEAL 4" P/SK	.25#	65.00
100 lb.	Gel Flush	.18#	18.00
	BULK CHARGE		
3.7 Ton	BULK TRK. MILES at 90 miles		316.35
0	PUMP TRK. MILES		N/C
1	PLUGS 4 1/2" Top Rubber Plug		35.00
		6.3% SALES TAX	64.03
		TOTAL	2096.68

T.D. 510'
 SIZE HOLE 6 3/4"
 MAX. PRESS. _____
 PLUG DEPTH _____
 PLUG USED _____

RECEIVED
 KANSAS CORPORATION COMMISSION
 DEC 14 2007
 CONSERVATION DIVISION
 WICHITA, KS

CSG. SET AT 502' VOLUME 8 Bbls
 TBG SET AT _____ VOLUME _____
 SIZE PIPE 4 1/2" - 10-5/16"
 PKER DEPTH _____
 TIME FINISHED _____

REMARKS: Rig up to 4 1/2" casing, Break circulation with 8 Bbls water. Pumped 5 Bbl Gel Flush, followed with 15 Bbls water spacer. Mixed 65 SKS Quick Set cement w/ 4" P/SK of KOL-SEAL at 13.5 lb. 2% gel. Shut down - washout Pump & Lines - Release Plug - Displace Plug with 8 Bbls water. Final Pumping at 300 PSI - Pumped Plug to 850 PSI. Pressure slowly bled off to 100 PSI (Possibly Third leak) wait a few minutes - Pressure back up to 400 PSI - slowly bleed off to 200 PSI - chase casing in with 200 PSI

NAME Ray T.
Dan Kimbark
Brad Butler
 UNIT NO. 185

EQUIPMENT USED Good cement returns to surface w/ 4 Bbls slurry
 NAME Brandon
 UNIT NO. 91