

KANSAS CORPORATION COMMISSION
 OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
 Please TYPE Form and File ONE Copy

Form CP-1
 September 2003
 This Form must be Typed
 Form must be Signed
 All blanks must be Filled

API # 15-009-20,476-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 3-6-1970

Well Operator: PYRAMID CORPORATION INC (Owner / Company Name) KCC License #: 5617 (Operator's)

Address: 1030 VINCENT LN City: WICHITA

State: KS Zip Code: 67206 Contact Phone: (316) 685-9695

Lease: PASCOE A Well #: 2 Sec. 11 Twp. 19S S. R. 15W East West

NW SW SW Spot Location / QQQQ County: BARTON

990 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 895' Cemented with: 100 Sacks

Production Casing Size: 5 1/2" Set at: 3540' Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3540-55'

Elevation: 1943 (G.L. / K.B.) T.D.: 3555 PBTD: _____ Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): ACCORDING TO THE RULES AND REGULATIONS OF THE STATE OF KANSAS

RECEIVED

MAR 13 2009

KCC WICHITA

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: MIKE KELSO Phone: (620) 938-2943

Address: P O BOX 467 City / State: CHASE KS 67524

Plugging Contractor: MIKE KELSO OIL CORP (Company Name) KCC License #: 31528 (Contractor's)

Address: SAME AS ABOVE Phone: (620) 938-2943

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
 Date: 3/9/09 Authorized Operator / Agent: Vicki White (Signature)

*DUSTY
 PWT*

W E L L L O G

DATE COMMENCED: February 16, 1970
 DATE COMPLETED: February 25, 1970

Pyramid Corporation, Inc.
 PASCO A-2
 100' N of NW SW SW
 Sec. 11-T19S-R15W
 Barton County, Kansas

ELEVATION 1943 K.B.

0	-	150'	Surface Clay & Red Clay
150	-	310'	Sand & Shale
310	-	430'	Shale
430	-	883'	Sand-Shale-Red Bed
883	-	915'	ANHYDRITE
915	-	1865'	Shale - Shells
1865	-	2235'	Lime & Shale
2235	-	2645'	Shale
2645	-	2829'	Shale & Lime
2829	-	3156'	Lime
3156	-	3159'	Shale
3159	-	3170'	Shale & Lime
3170	-	3184'	Lime
3184	-	3234'	Shale
3234	-	3244'	Lime - Shale
3244	-	3459'	Lime
3459	-	3481'	Shale
3481	-	3532'	Conglomerate
3532	-	3555'	Sand
3555	-		RTD

FORMATION DATA

ANHYDRITE	883
HEEBNER	3156
TORONTO	3170
DOUGLAS	3184
BR. LIME	3234
LANSING	3244
BASE LANSING	3459
CONGLOMERATE	3481
REAGEN SAND	3532
RTD	3555

SURFACE PIPE: Set new 20#
 8-5/8" casing at 895' with
 160 sks. Halco light & 125
 sks. Pozmix

PRODUCTION STRING: Set used
 5 1/2" pipe at 3540' with 125 sal
 saturated pozmix.

A F F I D A V I T

RECEIVED
 MAR 13 2009

KCC WICHITA

STATE OF KANSAS
 COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the
 facts and statements herein contained are true and correct to the
 best of his knowledge.



Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

THE PYRAMID CORPORATION, INC.
1030 VINCENT ST
WICHITA, KS 67206-1350

March 18, 2009

Re: PASCOE A #2
API 15-009-20476-00-00
11-19S-15W, 990 FSL 4950 FEL
BARTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after September 14, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550