

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form ACO-1  
September 1999  
Form Must Be Typed

**CONFIDENTIAL**

**WELL COMPLETION FORM**  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

**ORIGINAL**

Operator: License # 5144  
Name: Mull Drilling Company, Inc.  
Address: P.O. Box 2758  
City/State/Zip: Wichita KS 67201-2758  
Purchaser: N/A  
Operator Contact Person: Mark Shreve  
Phone: (316) 264-6366  
Contractor: Name: Pickrell Drilling Co., Inc.  
License: 5123  
Wellsite Geologist: Kent Crisler

Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  SWD  SLOW  Temp. Abandonment  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_

Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening  Re-perf.  Conv. to Enhr./SWD  
 Plug Back  Plug Back Total Depth  
 Commingled  Docket No. \_\_\_\_\_  
 Dual Completion  Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?)  Docket No. \_\_\_\_\_

9/7/04	9/16/04	9/17/04
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 007-22844 - 00 - 00

County: Barber  
C NE SE Sec. 6 Twp. 34 S. R. 11  East  West  
1980 feet from (S) N (circle one) Line of Section  
660 feet from (E) W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE (SE) NW SW  
Lease Name: Nurse Well #: 1-6  
Field Name: Rhodes SW

Producing Formation: N/A  
Elevation: Ground: 1418' Kelly Bushing: 1423'  
Total Depth: 4643' Plug Back Total Depth: \_\_\_\_\_

Amount of Surface Pipe Set and Cemented at 234' Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set \_\_\_\_\_ Feet  
If Alternate II completion, cement circulated from \_\_\_\_\_  
feet depth to \_\_\_\_\_ w/ \_\_\_\_\_ sx cmt.

**Drilling Fluid Management Plan** *(Data must be collected from the Reserve Pit)* P+A KJR 2/22/08  
Chloride content 59,000 ppm Fluid volume 600 bbls  
Dewatering method used Evaporation

Location of fluid disposal if hauled offsite: \_\_\_\_\_  
Operator Name: \_\_\_\_\_  
Lease Name: \_\_\_\_\_ License No.: \_\_\_\_\_  
Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West  
County: \_\_\_\_\_ Docket No.: \_\_\_\_\_

RECEIVED  
NOV 05 2004  
KCC WICHITA

KCC  
NOV 03 2004  
CONFIDENTIAL

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.


Signature: \_\_\_\_\_

Title: President/COO Date: 11/3/04

Subscribed and sworn to before me this 3<sup>rd</sup> day of November

Notary Public Tannis L. Tritt

Date Commission Expires: 3-26-07



**KCC Office Use ONLY**

Letter of Confidentiality Attached  
If Denied, Yes  Date: \_\_\_\_\_

Wireline Log Received  
 Geologist Report Received  
 UIC Distribution



# ALLIED CEMENTING CO., INC.

17392

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

M.L.

DATE <u>9-8-04</u>	SEC. <u>6</u>	TWP. <u>34s</u>	RANGE <u>11w</u>	CALLED OUT <u>2:30 AM</u>	ON LOCATION <u>3:00 AM</u>	JOB START <u>7:05 AM</u>	JOB FINISH <u>7:30 AM</u>
LEASE <u>Norse</u>		WELL # <u>1-6</u>	LOCATION <u>281 + 160 11s, 1E, 3/4s</u>	COUNTY <u>Barber</u>	STATE <u>KS</u>		
OLD OR NEW (Circle one) <u>NEW</u>			W. into				

CONTRACTOR Pickroll Drilling  
 TYPE OF JOB Surface  
 HOLE SIZE 12 1/4" TD. 240'  
 CASING SIZE 8 5/8 24.00 DEPTH 235'  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE 4 1/2" DEPTH 240'  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM 50  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT 15'  
 CEMENT LEFT IN CSG. 15'  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT 14 bbl Fresh Shut-in

OWNER Mull Drilling  
 CEMENT  
 AMOUNT ORDERED 185 sx 60:40:2  
+3% bcc  
 COMMON 111 # @ 7.85 871.35  
 POZMIX 74 @ 4.10 303.40  
 GEL 3 @ 11.00 33.00  
 CHLORIDE 6 @ 33.00 198.00  
 ASC \_\_\_\_\_ @ \_\_\_\_\_

EQUIPMENT  
 PUMP TRUCK CEMENTER Mike Rucker  
 # 265 HELPER Bill Mcadoo  
 BULK TRUCK  
 # 364 DRIVER Jerry Cashbury  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

RECEIVED  
 NOV 05 2004  
 KCC WICHITA  
 @ KCC  
 @ NOV 03 2004  
 @ CONFIDENTIAL  
 @  
 @  
 HANDLING 194 @ 1.35 261.90  
 MILEAGE 14 x 1.94 x .05 150.00  
 min chrg  
 TOTAL 1817.65

REMARKS:

50  
6 1/2" pipe on bottom break circulation  
7:05 am start Dead Current 185sx 60:40:2 +  
3% bcc @ 14.7 min @ 7:20 am stop  
Pumps Release wooden Plug start Disp  
4 1/2 bbl min @ 200 psi @ 14 bbl Fresh  
15' Disp. stop pumps leave 15' cement  
in casing @ 7:30 am cement did circulate  
circulate 50% to pit.

SERVICE  
 DEPTH OF JOB 235'  
 PUMP TRUCK CHARGE 0-300' 570.00  
 EXTRA FOOTAGE @ \_\_\_\_\_  
 MILEAGE 14 @ 4.00 56.00  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_

CHARGE TO: Mull Drilling  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

TOTAL 626.00

PLUG & FLOAT EQUIPMENT

MANIFOLD @ \_\_\_\_\_  
8 7/8 wooden Plug @ 55.00 55.00  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 TOTAL 55.00

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment  
 and furnish cementer and helper to assist owner or  
 contractor to do work as is listed. The above work was  
 done to satisfaction and supervision of owner agent or  
 contractor. I have read & understand the "TERMS AND  
 CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Mike Kern

Mike Kern  
 PRINTED NAME

