

State of Kansas



15-051-20217-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Walker of Rains & Williamson Oil Co. has this
date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Wichita, Ks.

Lease Name: Boschowitzki Well No. 1

Location: NW SW SE Sec. 8 Twp. 13 Rge. 18 (E)(W) X

County Ellis Total Depth 3865 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace

70 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

Very truly yours,

Leo F. Murray
Conservation Division Agent