



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date June 20, 19 58, authorized the following plugging operation:

Operator's Full Name: Transit Corporation and Davis Bros.

Complete Address: 1516 Liberty Bank Bldg., Oklahoma City, Okla.

Lease Name: Haysland Well No. 1

Location: NW NW NW Sec. 7 Twp. 11 Rge. 21 (E) (W)

County: Trego Total Depth: 3808

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Dry Hole

Operator was instructed to plug well as follows:

Gun pits circulate hole with heavy mud. Set cementing plug at 600 feet and displace 20 sacs cement through drill pipe. Heavy mud to 155 feet set dementing plug 1/2 sac hulls and 15 sacs of cement. Heavy mud to 40 feet 1/2 hulls and 10 sacs cement to bottom of cellar.

Very truly yours,

Gilbert P. Leiker

Signed: Gilbert P. Leiker
Conservation Division Agent

6-24-1958