

15-051-20861-00-00

KANSAS

Form CP-3
Rev. 6-4-68



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
2-21-1973
FEB 21 1973
CONSERVATION DIVISION
Wichita, Kansas

INV.
Joseph S. Gross

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas

Lease Name Raymond Haneke Well No. 1-V

Location SW NE SW Sec. 18 Twp. 11 Rge. (E) (W) 20

County Ellis Total Depth 3730'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 6 P Day 19 Month 2 Year 1973

The above well was plugged as follows:

RTD. 3730' 10 3/4 csg set at 277' cwc: Cmt. Mat. 50-50 poz cmt W/6% total gel.

Drilled 9" hole from 277' to anhydrite. (1550')

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 80 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 15 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 2/22/73

INV. NO. 7013-W