

15-051-22864-00-00

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,864

FORM CP-3
1-8-82
RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1982
CONSERVATION DIVISION
Wichita, Kansas

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Capital Oil Corporation

Complete Address 411 Farmers & Bankers Bld., Wichita, Ks. 67202

Lease Name Griswald Well No. 1

Location C of NW NE Sec. 20 Twp. 11 Rge. 20 (East) (West)

County Ellis Total Depth 3820' 124'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc.

Address 801 Union Ctr., Wichita, Ks. 67202 License No. _____

Operation Completed: Hour: 4:00 AM Day: 26 Month: FEB. Year: 19 82

Plugging Operations attended by Agent?: All XXX Part _____ None _____

The above well was plugged as follows:

8 5/8"-235' S.P. cuc. W/ 185 sacks common 2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. and 8 5/8" plug.

Spot W/ drill stem W/ heavy mud between all plugs.

1st plug @ 920' W/ 70 sacks cement

2nd plug @ 230' W/ 40 sacks cement

3rd plug -solid bridge of hulls and plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 235' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not-being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED

DATE 3-2-82

INV. NO. 9519-W