

15-051-20683-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 13 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum, Inc.  
Complete Address 300 West Douglas Wichita, Kansas  
Lease Name Cromb Well No. 1  
Location SW NW NW Sec. 22 Twp. 11 Rge. (E) (W) 20  
County Ellis Total Depth 3710'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Garvey Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 10 A Day 11 Month 11 Year 1970

The above well was plugged as follows:

RTD 3710' 8 5/8 csg set at 220' cwc 175 sk Cmt. Mat. 100 sk reg poz 6%.  
Gunned pits, circulated heavy mud, set cementing <sup>plug</sup> at 720' and displaced 70 skcmt thru  
drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru drill  
pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red F. Massey  
Well Plugging Supervisor

DATE 11-13-70

INV. NO. 2852-W