

15-051-20750-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED  
STATE CORPORATION COMMISSION  
7-28-1971  
JUL 28 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum, Inc.

Complete Address 300 W. Douglas Wichita, Kansas

Lease Name Huck "D" Well No. 1

Location A/ S/2 S/2 NW Sec. 32 Twp. 11 Rge. (E) (W) 20

County Ellis Total Depth 3585'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Garvey Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 9 A Day 26 Month 7 Year 1971

The above well was plugged as follows:

BTD 3585' 8 5/8 csg set at 216' cwc 175 sk Cmt. Mat. reg poz 6% gel

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Lew J. Messing  
Well Plugging Supervisor

INVOICED

DATE 7-29-71

INV. NO. 4066-10