

15-051-20217-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
*3-11-1968*  
MAR 11 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Wichita, Kansas

Lease Name Boschowitzki Well No. 1

Location NW SW SE Sec. <sup>*33*</sup>8 Twp. <sup>*11*</sup>13 Rge. <sup>*20W*</sup>18 (E)  (W)

County Ellis Total Depth ~~33865~~ 3865

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Co. Tools

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 3:30 P Day 7 Month 3 Year 1968

The Above well was plugged as follows:

RTD 3865' 8 5/8 csg set at 245' cwc 160 sc. Cem. Mat. 100 sc 50-50poz cem. W/6% gel.  
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.  
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Rio F. Massey*  
Well Plugging Supervisor

DATE *3/11/68*

INV. NO. *17390-W*