

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 33325
Name: Petroleum Development Corporation
Address: 1775 Sherman Street, Suite 3000
City/State/Zip: Denver, CO 80203
Purchaser: Riley Natural Gas Company
Operator Contact Person: Larry Robbins
Phone: (303) 860-5800
Contractor: Name: Schaal Drilling, Co. LLC & Advanced Drilling Technologies, LLC
License: 38775 & 33532
Wellsite Geologist: N/A

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____

Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____

Deepening Re-perf. Conv. to Enhr./SWD

Plug Back Plug Back Total Depth

Commingled Docket No. _____

Dual Completion Docket No. _____

Other (SWD or Enhr.?) Docket No. _____

<u>07/01/2008</u>	<u>07/05/2008</u>	<u>09/22/2008</u>
Spud Date or Recompletion Date.*	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 023-20831-0000 ²¹⁹³⁷

County: Cheyenne

 NW NE NE Sec. 3 Twp. 4 S. R. 42 East West

395 feet from S / (N) (circle one) Line of Section

1307 feet from (E) / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) (NE) SE NW SW

Lease Name: Feikert-Klie Well #: 41-3

Field Name: Cherry Creek Niobrara Gas Area

Producing Formation: Niobrara

Elevation: Ground: 3721' Kelly Bushing: 3733'

Total Depth: 1710' Plug Back Total Depth: 1666'

Amount of Surface Pipe Set and Cemented at 8 joints @ 346 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from _____

feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan AH I NUR 3-11-09
(Data must be collected from the Reserve Pit)

Chloride content 5000 ppm Fluid volume 50 bbls

Dewatering method used Evaporation

Location of fluid disposal if hauled offsite: _____

Operator Name: _____

Lease Name: _____ License No.: _____

Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West

County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Jerry Jones


Title: Regulatory Agent Date: February 05, 2009

Subscribed and sworn to before me this _____ day of _____

20 09

Notary Public: Susan Holly Cobb My Commission Expires 10/04/2011

Date Commission Expires: 10/04/2011



KCC Office Use ONLY

Letter of Confidentiality Received
If Denied, Yes Date: _____

Wireline Log Received

Geologist Report Received

UIC Distribution

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 06 2009

Operator Name: Petroleum Development Corporation Lease Name: Feikert-Klie Well #: 41-3
 Sec. 3 Twp. 4 S. R. 42 East West County: Cheyenne

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No (Attach Additional Sheets) Samples Sent to Geological Survey <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (Submit Copy) List All E. Logs Run: CDL, CNL, Dual Induction, CBL	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Name Top Datum Niobrara 1516' <div style="text-align: right;"> RECEIVED KANSAS CORPORATION COMMISSION FEB 06 2009 CONSERVATION DIVISION WICHITA, KS </div>
--	---

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	10"	7"	17#	346'	Type I/II	85	
Production	6 1/8"	4 1/2"	10.5 #	1686'	Type I/II	75	2% KCL

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	
			Depth
2	1532'-1544'	500 gal 15% HCL, 70 Quality N2 foam, 304 bbls Lightning 15# fluid system, 97120 lbs of Ottawa 12/20 mesh sand 4200 lbs of SB Excel 12/20 resin coated sand 266 MSCF N2	1532'-1544'

TUBING RECORD	Size 2 3/8"	Set At 1574'	Packer At	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr. 10/14/2008		Producing Method <input checked="" type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls. 0	Gas Mcf 49	Water Bbls. 0	Gas-Oil Ratio n/a
Gravity				

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-18.)

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____

SCHAAL DRILLING, CO.
46881 HWY 24
BURLINGTON, CO. 80807
719-346-8032
FIELD REPORT
SURFACE CASING, DRILLING AND CEMENTING

DRILLING DATE 7-01-08

WELL NAME & LEASE # Feikert-Klie 41-3

MOVE IN, RIG UP, DIG PITS ETC. DATE 6-30-08 TIME 12:15 AM PM

SPUD TIME 7:15 AM PM SHALE DEPTH 260 TIME 9:15 AM PM

HOLE DIA. 10 FROM 0 TO 338 TD TIME 10:00 AM PM

CIRCULATE, T.O.O.H., SET 332.92 FT CASING 345.92 KB FT DEPTH

8 JOINTS 7 OD #/FT 14 15.5 17 20 24

PUMP 85 SAC CEMENT 546 GAL.DISP. CIRC. 5 BBL TO PIT

PLUG DOWN TIME 11:15 AM PM DATE 7-01-08

CEMENT LEFT IN CSG. 20 FT TYPE: PORTLAND CEMENT I/II ASTM C 150
CENTRALIZER 1 CEMENT COST \$ 1662.08

ELEVATION 3721
+12KB 3733


PIPE TALLY

1. 41.75
 2. 41.72
 3. 41.27
 4. 41.31
 5. 41.73
 6. 41.71
 7. 41.72
 8. 41.73
 - 9.
 - 10.
 - 11.
 - 12.
 - 13.
 - 14.
- TOTAL 332.92

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 06 2009

CONSERVATION DIVISION
WICHITA, KS



A DIVISION OF ADVANCED DRILLING TECHNOLOGIES, LLC.

LONGHORN CEMENTING CO.

P.O. BOX 203 YUMA, COLORADO 80759
 Phone: 970-848-0799 Fax: 970-848-0798

FIELD SERVICE TICKET
 AND INVOICE

DATE 2/5/08 TICKET NO. 1596

DATE OF JOB <u>2/5/08</u>	DISTRICT	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:	
CUSTOMER <u>PDC</u>	LEASE <u>FEIKERT, KLEC 41-3</u>	WELL NO.						
ADDRESS	COUNTY	STATE						
CITY	STATE	SERVICE CREW <u>Thomas / DAUR</u>						
AUTHORIZED BY	EQUIPMENT <u>Pump 112</u>							
TYPE JOB: <u>1/5</u>	DEPTH FT.	CEMENT DATA: BULK <input type="checkbox"/>			SAND DATA: SACKS <input type="checkbox"/>		TRUCK CALLED <u>111</u>	DATE AM PM
		SACKS	BRAND	TYPE	% GEL	ADMIXES	ARRIVED AT JOB	AM PM
SIZE HOLE:	DEPTH FT.	<u>75</u>	<u>A</u>	<u>III</u>			START OPERATION	AM PM
SIZE & WT. CASTING <small>NEW OR USED</small>	DEPTH FT.						FINISH OPERATION	AM PM
SIZE & WT. D PIPE OR TUBING	DEPTH FT.						RELEASED	AM PM
TOP PLUGS	TYPE:	WEIGHT OF SLURRY: <u>15</u>	LBS. / GAL.	LBS. / GAL.				
		VOLUME OF SLURRY: <u>17</u>						
<u>TD 1710</u>	<u>85</u>	SACKS CEMENT TREATED WITH <u>2</u> % OF <u>Calcium</u>			MILES FROM STATION TO WELL			
<u>1-5TD</u>	MAX DEPTH <u>1672</u> FT.	MAX PRESSURE <u>2000</u> P.S.I.						

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only these terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without written consent or an officer of Advanced Drilling Technologies, LLC.

SIGNED: _____

(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM / PRICE REF. NUMBER	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
<u>001-1</u>	<u>Depth Charge / Mileage / cement</u>				<u>4200</u>
<u>300-12</u>	<u>7" cementizer</u>		<u>1</u>		<u>36</u>
<u>400-3</u>	<u>KCL</u>		<u>3 bags</u>		<u>60</u>
<u>500-2</u>	<u>Calcium</u>		<u>1 bag</u>		<u>50</u>
	<u>20 BBI Check</u>				
	<u>W.P. 75 5% cement @ 15'</u>				
	<u>Drop Plug & D. replace 28' BBI</u>				
	<u>4-20 5/8" plug @ 2000 PSI</u>				
RECEIVED KANSAS CORPORATION COMMISSION FEB 06 2008 CONSERVATION DIVISION WICHITA, KS					
SUB TOTAL					<u>4346</u>
SERVICE & EQUIPMENT				% TAX ON \$	
MATERIALS				% TAX ON \$	
TOTAL					

ACID DATA:			
	GALLONS	%	ADDITIVES
HCL			
HCL			

SERVICE & EQUIPMENT	% TAX ON \$	
MATERIALS	% TAX ON \$	
TOTAL		

SERVICE REPRESENTATIVE <i>[Signature]</i>	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY <i>[Signature]</i>
FIELD SERVICE ORDER NO.	(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)