

State of Kansas



15-195-20052-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1967
12-6-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Joe Gerritzen of Braden Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Gerritzen guarantees payment of the plugging fee.

Operator's full Name: Lee Phillips Oil Company & Braden Drilling, Inc.,

Complete Address: 1532 Wichita Plaza, Wichita, Kansas.

Lease Name: Taylor Well No. 1

Location: SW-NW-NW Sec. 10 Twp. 11 Rge. (E)(W) 21

County Trego Total Depth 3735' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gerritzen was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.
Dakota section from 600' to 800'.

Circulate hole with heavy mud. Pull DP to 800' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent