



15-195-20904-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Earl Evers of Evers Consulting Serv has this date requested permission to plug the following described well:

Operator's Full Name: Voyager Petroleum Inc  
Complete Address: Petroleum Bldg - Suite 800; 110 Sixteenth; Denver, Colo 80202  
Lease Name: Schubert Well No. 1  
Location: NW-NW Sec. 31 Twp. 11 Rge. 21 (E) (W)  
County: Mingo Total Depth: 4160  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereafter indicated: —

Mr. Evers was instructed to plug the well as follows:

8 5/8" - 259' SP c/w w/190 SK cmt. -> 4 1/2" set @ 4160 w/240 SK cmt -> Plug back at 3574 w/plug + 50' sand + 5 SK cmt -> Top Pipe 3726' -> Shot casing 3230' -> Recovered 3230' -> Ordered 140 SK cmt 50% poz mix 4% gel 3% CP-CL -> 23 SK gel -> 5 SK hulla -> 8 5/8" plug: Pump in w/pump truck - 4 SK hulla -> 15 SK gel -> 70 SK cmt -> 8 gel -> Rel Plug -> 70 SK cmt

(Cont by Sum)

Very truly yours,

Dennis L. Hammon  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

JAN 19 1982  
1-19-1982  
CONSERVATION DIVISION  
Wichita, Kansas