



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

RECEIVED
 STATE CORPORATION COMMISSION
 11-25-1959
 NOV 25 1959
 CONSERVATION DIVISION
 Wichita, Kansas

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date Nov 21, 1959, authorized the following plugging operation:

Operator's Full Name: Pet Inc.
 Complete Address: 352 Broadway, Wichita Kans.
 Lease Name: Neber Well No. 1
 Location: Se Ne Se Sec. 32 Twp. 11 Rge. 21 (E) (W)
 County: Drego Total Depth: 4055
 Oil Well Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Run Potts circulate hole with heavy mud, set
cementing plug at 600' and displace 20 sack cement
thru drill pipe, heavy mud to 200' set cementing
plug and displace 15 sack cement, heavy mud to
40' set and tie cementing plug in place dump 1/2
sack hulls and 10 sack cement, cementing to base of
cellar.

Very truly yours,

Signed: Herbert O. Lecker
 Conservation Division Agent