



15-195-20227-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
8-2-1972
AUG 2 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Nossaman of Thomas Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Nossaman guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: McCall Well No. 1

Location: SW-SW-NE Sec. 6 Twp. 11 Rge. (E)(W) 22

County: Trego Total Depth 3990' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nossaman was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 550'.

Circulate hole with heavy mud. Pull DP to 775' and displace 110 Cu. Ft. cement thru DP. Pull DP to 250' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent