

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
2-15-73
FEB 15 1973
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., Inc. has this
date requested permission to plug the following described well:Mr. Unruh guarantees payment of the plugging fee.Operator's full Name: Bankoff Oil Company,Complete Address: 1119 Sherman, Great Bend, Kansas.Lease Name: Bollig Well No. 6Location: CE/2-E/2-SW Sec. 28 Twp. 9 Rge. (E)(W) 25County: Graham Total Depth 4071' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Unruh was instructed to plug the well as follows:254'--8 5/8" Surface casing, cement circulated with 175 Sx.4070'--5 1/2" casing cemented on bottom with 100 Sx. Well plugged back to
4048'. Top perforations from 3949' to 3953'.Sand well back to 3900' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,

Conservation Division Agent