

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

RECEIVED
APR 23 4 23 PM '82
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Don Davis of Allied Cementing has this date requested permission to plug the following described well:

Operator's Full Name: Energy Producers Inc.

Complete Address: 8020 E. Central, Suite 150 Wichita, KS 67206

Lease Name: Sauer Well No. #1

Location: CNW4 NE4 Sec. 28 Twp. 9 Rge. 25 (E) (W)

County: Graham Total Depth: 4100

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Davis was instructed to plug the well as follows:

8 5/8" @ 210' w/150 sx; 5 1/2" @ 4097 w/125 sx open hole;
Plug back 4093; perf 4078, 3895; squeezed @ 2236'
w/175 sx circ to surface; Ordered 300 sx 50/50 permix
6% gel - 3% cc, 16 gel, 3 hulls + 5 1/2" plug Pumped in
w/pump truck 3 hulls and 75 cmt. m. bottom; spaced
w/16 gel; released plug + 225 cmt. no pressure - 4/16/82
ran line, cement down 250-300' Allied returned to location
filled to surface.

Very truly yours,

Dennis L. Hamel
Conservation Division Agent